

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-48218	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> RIGSKID				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: N/A	
2. NAME OF OPERATOR: XTO Energy, Inc.				9. WELL NAME and NUMBER: State of Utah 17-8-28-12X	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. B <small>CITY</small> Farmington <small>STATE</small> NM <small>ZIP</small> 87401				10. FIELD AND POOL, OR WILDCAT: Ferron Sandstone	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1332' FNL x 582' FWL in Sec 28, T17S, R8E RIGSKID AT PROPOSED PRODUCING ZONE: same				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 3.75 miles West of Huntington, Utah				12. COUNTY: Emery	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1475'		16. NUMBER OF ACRES IN LEASE: 1800.92		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) None		19. PROPOSED DEPTH: 3,950		20. BOND DESCRIPTION: UTB-000138	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6791' Ground Elevation		22. APPROXIMATE DATE WORK WILL START: 9/15/2006		23. ESTIMATED DURATION: 2 weeks	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12.25"	8.625"	J-55	24#	300	Class G	+/- 210 sxs	1.18 ft3/sx 15.7 ppg
7.875"	5.5"	J-55	15.5#	3,950	CBM light wt - lead	+/- 230 sx	4.15 ft3/sx 10.5 ppg
					Class G	+/- 210 sx	1.62 ft3/sx 14.2 ppg

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <u>Kyla Vaughan</u>	TITLE <u>Regulatory Compliance Tech</u>
SIGNATURE <u>Kyla Vaughan</u>	DATE <u>7/26/2006</u>

(This space for State use only)


API NUMBER ASSIGNED: 43-015-30699

APPROVAL:

RECEIVED
JUL 31 2006
DIV. OF OIL, GAS & MINING

Range 8 East

Township 17 South



Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

NOTE:

UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG	
39°19'06.739" N	111°02'10.369" W

Location:

THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:

THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:

THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:


BASIS OF ELEVATION OF 6495' BEING AT THE SOUTHEAST SECTION CORNER OF SECTION 20, TOWNSHIP 17 SOUTH, RANGE 8 EAST, SALT LAKE BASE & MERIDIAN, AS SHOWN ON THE RED POINT QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:

PROPOSED DRILL HOLE LOCATED IN THE SW 1/4 NW 1/4 OF SECTION 28; BEING 1331.55' FROM THE NORTH LINE AND 582.01' FROM THE WEST LINE OF SECTION 28, T17S, R8E, SALT LAKE BASE AND MERIDIAN.

Surveyor's Certificate:

I, ALBERT J. SPENSKO, A REGISTERED PROFESSIONAL LAND SURVEYOR, HOLDING CERTIFICATE 146652 STATE OF UTAH, DO HEREBY CERTIFY THAT THE INFORMATION ON THIS DRAWING IS A TRUE AND ACCURATE SURVEY BASED ON DATA OF RECORD AND WAS CONDUCTED UNDER MY PERSONAL DIRECTION AND SUPERVISION AS SHOWN HEREON.



GRAPHIC SCALE



TALON RESOURCES, INC.

195 N. 100 W., P.O. Box 1230
Huntington, Utah 84528
Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



State of Utah #17-8-28-12
Section 28, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-1	Date: 02/22/06
Sheet 1 of 4	Scale: 1" = 1000'
	Job No. 2059



July 26, 2006

RECEIVED
JUL 31 2006
DIV. OF OIL, GAS & MINING

Utah Division of Oil, Gas & Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

RE: State of Utah 17-8-28-12X Rig skid

Dear Diana,

Please see enclosed APD for the State of Utah 17-8-28-12X well location. This APD is for a "rig skid" well. The original well bore (State of Utah 17-8-28-12) was abandoned due to severe hole deviation underneath the surface casing. The original well bore P&A has been completed. The P&A report, and the well completion report has been submitted to your office.

Regards,

A handwritten signature in black ink that reads 'Kyla Vaughan'.

Kyla Vaughan
Regulatory Compliance

Application for Permit to Drill Surface Use Plan

Company:

XTO Energy Inc.

Well No.

State of Utah 17-8-28-12X

Location:

Sec. 28, T17S, R8E

State Lease No.

ML-48218

THIRTEEN POINT SURFACE USE PLAN

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

1) Existing Roads:

- a) Proposed route to location: The proposed route to location is show on **Exhibit "A"** and is from the Red Point Quadrangle 7.5 minute series USGS quadrangle map
- b) Location of proposed well in relation to town or other reference point: The well is located approx. 3.75 miles west of Huntington, Utah. Go west on 4th North from Huntington 1.9 miles, turn left go 2.7 miles, turn left go .5 mile to location.
- c) Contact the County Road Department for use of county roads. The use of Emery County roads will require an encroachment permit from the Emery County Road Department. No encroachment permit will be required.
- d) Plans for improvement and/or maintenance of existing roads: All existing roads that will be used to the well location will be maintained to their current conditions or better.
- e) Other: None

2) Planned Access Roads:

- a) Location (centerline): Starting from a point along an existing road in the NW/4 of Section 28, T17S, R8E.
- b) Length of new access top be constructed: No new access will be constructed for this well. Located on the State of Utah 17-8-28-12 pad. This is a rig skid.
- c) Length of existing roads to be upgraded: No additional upgrades should be necessary to existing roads.
- d) Maximum total disturbed width: Typically new access roads require up to 60' of disturbed width which includes ROW for gas and water pipe lines and electric service.
- e) Maximum travel surface width: 25' or less
- f) Maximum grades: Maximum grades will not exceed 10% after construction.
- g) Turnouts: No turnouts are planned at this time.
- h) Surface materials: Only native materials will be used if additional construction is required. If necessary, gravel or rock maybe purchased and used to improve road conditions and travel.

- i) Drainage (crowning, ditching, culverts, etc): Roads will be re-crowned and bar ditches, if necessary, will be located along either side. 18"-24" culverts will be installed as necessary.
 - j) Cattle guards: No cattle guards are planned at this time. If necessary cattle guards will be specified in the stipulations.
 - k) Length of new and/or existing roads which lie outside the lease or unit boundary for which a BLM/state/fee right-of-way is required: None
 - l) Other:
 - i) Surface disturbance and vehicular travel will be limited to the approved location and access road. Any additional area needed must be approved by the State of Utah in advance.
 - ii) If a right-of-way is necessary, no surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. The holder will adhere to conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.
 - iii) If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of-way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.
 - iv) If at any time the facilities located on public lands authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change) the State of Utah will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental, or other financial obligations determined by the State of Utah.
 - v) If the well is not productive, the access road will be rehabilitated or brought to Resource (Class III) Road Standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Field Office Manager will be notified so that temporary drainage control can be installed along the access road.
- 3) Location of Existing Wells -on a map, show the location of all water, injection, disposal, producing and drilling wells within a one mile radius of the proposed well, and describe the status of each: **See Exhibit "B".**
- 4) Location of Production Facilities:
- a) On-site facilities: Typical on-site facilities will consist of a wellhead, gas flow line, water flow line, artificial lifting system (pumping unit), 2 phase separator, gas measurement, water measurement, electronics, a heated enclosure/building for weather and environmental protection and chemical injection equipment (as required). All production and measurement shall conform to the provisions of 43 CFR § 3162.7 and Onshore Oil and Gas Order No. 4, if applicable.
 - b) All permanent (in place for six months or longer) structures constructed or installed on the well site location will be painted a flat, non reflective color to match the standard environmental colors, as specified by the COA's in the APD. All facilities will be painted within six months of installation. Facilities required complying with the Occupational Safety and Health Act (OSHA) may be excluded.

- c) Off-site facilities: Off-site facilities are located at the CDP station and include compression, processing, separation, tanks, pits, electronics and produced water disposal (SWD) well.
- d) Pipelines: The well will be produced into gas and water pipelines (sizes to be determined) and transported to existing pipelines. **Pipeline will follow the same route for the State of Utah 17-8-28-12.**
- e) Power lines: Power lines are located underground in the same ROW as the water and gas pipe lines.

5) Location and Type of Water Supply:

- a) All water needed for drilling purposes will be obtained from (describe location and/or show on a map): All water required for drilling will be purchased from a local municipal water supply. If possible, currently produced coal well water may also be used after receiving any necessary permits. Water will be trucked to location by a third party trucking company who specializes in water hauling.
- b) Water obtained on private land, or land administered by another agency, will require approval from the owner or agency for use of the land.

6) Source of Construction Material:

- a) Pad construction material will be obtained from (if the source is Federally owned, show location on a map): All construction material will be purchased from private landowners or a commercial gravel/materials pit. The use of materials will conform to 43 CFR § 3610.2-3, if applicable.
- b) The use of materials under State of Utah jurisdiction will conform to 43 CFR § 3610.2-3, if applicable.

7) Methods of Handling Waste Disposal:

- a) Describe the methods and locations proposed for safe containment and disposal of waste material, e.g. cuttings, produced water, garbage, sewage, chemicals, etc. The reserve pit will be located along the edge and within the boundaries of the designated well pad. The walls of the pit will be sloped at no greater than 2 to 1 and will be lined with a synthetic material of approximately 12 mils in thickness. The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. The amount of time the pit may remain open will typically be specified by the COA's. Once dry, the liner will be cut and removed at the mud line and the pit will be covered and buried in place.
- b) Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.
- c) Sewage from trailers and chemical portable toilets will be removed on a regular basis by a third party contractor and disposed of at an authorized sanitary waste facility.
- d) Any and all chemicals used during the drilling and completion of the well will be kept to a minimum and stored within the boundaries of the well pad. The third party chemical contractor will be responsible for containment and clean-up and removal of all spilled chemicals on location.

8) Ancillary Facilities: No ancillary facilities will be required during the drilling or completion of the well.

9) Well Site Layout -depict the pit, rig, cut and fill, topsoil, etc. on a plat with a scale of at least 1"=50'. **See Exhibit "C" & "D".**

- a) All equipment and vehicles that will be used to drill and complete this well will remain within the boundaries of the approved wellpad. Any equipment and or vehicles park or stored off of the location will be considered trespassing on federal lands and will NOT be tolerated.
- b) Materials obtained from the construction of location, like topsoil and vegetation will be stock piled as indicated and permitted by the approved APD. The stock piles themselves may be outside the approved boundaries of the well pad.

10) Plans for Restoration of the Surface:

- a) The top 6 inches of topsoil material will be removed from the location and stockpiled separately on: Adjacent Land or as specified by the approved APD.
- b) Topsoil along the access road will be reserved in place adjacent to the road.
- c) Within 30-45 days after completion of well, all equipment that is not necessary for production shall be removed.
- d) The reserve pit and that portion of the location not needed for production will be reclaimed 90-120 days after completion of the well.
- e) Before any dirt work to restore the location takes place, the reserve pit must be ready for burial.
- f) All road surfacing will be removed prior to the rehabilitation of roads.
- g) Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle use.
- h) All disturbed areas will be re-contoured to replicate the natural slope.
- i) The stockpiled topsoil will be evenly distributed over the disturbed area.
- j) Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.
- k) Seed will be broadcast or drilled between September and November, or at a time specified by the BLM and or state. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.
- l) The following seed mixture will be used: As specified in the conditions of approval
- m) If necessary, an abandonment marker will be one of the following, as specified by the State of Utah:
 - i) at least four feet above ground level,
 - ii) at restored ground level, or
 - iii) below ground level.
 - iv) In any case the marker shall be inscribed with the following: operator name, lease number, well name and surveyed description (township, range, section and either quarter-quarter or footages).

n) Additional requirements: None

11) Surface and Mineral Ownership: Both the surface and minerals are owned by the State of Utah.

12) Other Information:

- a) Archeological Concerns: An approved contractor will submit the appropriate reports to the agency as required. Special stipulations will be included in the COA's of the approved APD.
- b) The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the State of Utah Field Office. Within five (5) working days, the State of Utah will inform the operator as to:
 - i) whether the materials appear eligible for the National Register of Historic Places;
 - ii) the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
 - iii) a time frame for the State of Utah to complete an expedited review under 36 CFR § 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the State of Utah are correct and that mitigation is appropriate.
- c) If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the State of Utah will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The State of Utah will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the State of Utah that the required mitigation has been completed, the operator will then be allowed to resume construction.
- d) Threatened and Endangered Species Concerns: An approved contractor will submit the appropriate reports as required. Special stipulation will be included in the COA's of the approved APD.
- e) Wildlife Seasonal Restrictions: Current wildlife restrictions and closure dates are specified in the BLM's Environmental Impact Statement.

13) The Drilling Program is attached: **See Exhibit "E"**.

14) Lessee's or Operator's Representatives and Certification:

Permitting & Compliance:

Kyla Vaughan
Regulatory Compliance
XTO Energy Inc.
2700 Farmington Avenue, Bldg K, Suite 1
Farmington NM 87401
505-324-1090

Drilling & Completions:


Greg Vick
Drilling Engineer
XTO Energy Inc.
2700 Farmington Avenue, Bldg K, Suite 1
Farmington NM 87401
505-324-1090

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by **XTO Energy Inc.** and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided by **XTO Energy Inc.** This statement is subject to the provisions of 18 U.S.C. § 1001 for the filing of a false statement.

Signature Kyla Vaughan



Date 7/26/06



Map created with TOPO!® ©2003 National Geographic (www.nationalgeographic.com/topo)

EXHIBIT A

ELEVATION OF UNGRADED GROUND AT LOCATION STAKE = 6789.0'
ELEVATION OF GRADED GROUND AT LOCATION STAKE = 6788.5'



Talon Resources, Inc.

195 North 100 West P.O. Box 1230
Huntington, Utah 84528

Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



LOCATION LAYOUT
Section 28, T17S, R8E, S.L.B.&M.
State of Utah #17-8-28-12X

Drawn By: J. STANSFIELD
Checked By: L.W.J.




Drawing No. A-2
Date: 01/09/06

Scale: 1" = 50'


Sheet 2 of 4

Job No. 2059

Revision: 06/29/06
Job No: 2515



SLOPE = 1 1/2 : 1
(EXCEPT PIT)
PIT SLOPE = 1 ; 1



Talon Resources, Inc.

195 North 100 West P.O. Box 1230
Huntington, Utah 84528

Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



TYPICAL CROSS SECTION
Section 28, T17S, R8E, S.L.B.&M.
State of Utah #17-8-28-12X

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. C-1	Date: 01/09/06
	Scale: 1" = 40'
Sheet 3 of 4	Job No. 2059

APPROXIMATE YARDAGES

CUT

(6") TOPSOIL STRIPPING = 750 CU. YDS.

REMAINING LOCATION = 5,170 CU. YDS.

TOTAL CUT = 6,590 CU. YDS.

TOTAL FILL = 4,140 CU. YDS.

XTO ENERGY INC.
State of Utah 17-8-28-12X
Drilling Data for APD
July 26, 2006

Location: 1332' FNL & 582' FWL, Sec 28, T17S, R 8E

Projected TD: 3,950'
Approximate Elevation: 6,789'

Objective: Ferron Coal/Sand
KB Elevation: 6,801'

1) Mud Program:

INTERVAL	0' to 300'	300' to 3950'
HOLE SIZE	12.25"	7.875"
MUD TYPE	Air Drill	Air/LSND / Gel Chemical
WEIGHT	N/A	8.4 - 8.6
VISCOSITY	N/A	45 - 60
WATER LOSS	N/A	8 - 10

- a) Air drill to TD unless excessive water flow is encountered then switch to water based mud. If mud is required, use fibrous materials as needed to control seepage and lost circulation. Pump high viscosity sweeps as needed for hole cleaning. Raise viscosity at TD for logging. Reduce viscosity after logging for cementing.
- b) The blooie line will be approximately 100' in length and will extend in a straight line from below the rotating head as indicated in the BOP schematic. An automatic spark-type igniter will be fixed to the end of the blooie line and set to provide a continuous spark to ignite and burn any produced hydrocarbons and/or gases.
- c) If necessary, de-dusting will be accomplished with a small pump, waterline and spray nipple positioned near the end of the blooie line to provide a continuous spray of water.
- d) Sufficient mud materials will be stored on location to maintain well control and combat lost circulation problems that might reasonably be expected.
- e) The BOP system will be consistent with API RP 53 and Onshore Oil and Gas Order No. 2. Pressure tests of the surface casing and all BOP equipment subject to pressure will be conducted before drilling the surface casing shoe. Blowout preventer controls will be installed prior to drilling the surface casing shoe and will remain in use until the well is completed or abandoned. Ram preventers shall be inspected and operated daily. Annular preventers shall be inspected and operated weekly to ensure good mechanical working order. The inspections and tests shall be recorded in the drilling log and daily drilling report. See the attached BOP and choke manifold schematic.

2) Casing Program:

Length	Weight	Grade	Coll Pressure	Burst Pressure	Joint Strength	ID	Drift	SF Collapse	SF Burst	SF Tension
8.625 in, ST&C surface casing set in a 12.25 in hole										
300	24	J-55	950	2,950	272	8.097	7.97	7.30	22.66	37.78
5.5 in, ST&C production casing set in a 7.875 in. hole										
3,950	15.5	J-55	4,040	4,810	202	4.95	4.83	2.36	2.81	3.30

EXHIBIT E

3) Well Heads:

- a) Casing Head: Install Larkin Fig 92 (or equivalent), 10" nominal, 2,000 psig WP (4,000 psig test) with 8-5/8" 8rnd thread on bottom and 10-3/4" 8rnd thread on top. NU BOP and choke manifold (see attached schematic). Stack to consist of drilling spool with choke and kill lines, double rams with pipe rams on top, blind rams on bottom. Use cold water and test BOP to 250 psi low and 1,000 psi high. Record all tests on the IADC report. Inspect accumulator and closing unit to ensure that pre-charge pressures and oil levels are within API Specifications and report same on IADC report.
- b) Tubing Head: Larkin Fig 612 (or equivalent), 5,000 psig WP (5,000 psig test), 5-1/2" SOW (or 8rnd female thread) on bottom, 7-1/16" 5,000# flange on top w/2 - 3" LPOs.

4) Cement Program: Slurry design may change slightly, but design is to circulate cement to surface on both casing strings.

- a) Surface: 210 sx of Class G cement (or equivalent) containing 2% KCl, 1/4 % Flocele and dispersant mixed at 15.7 ppg & 1.18 ft³/sk.

- i) Slurry volume is 290 ft³, 200% excess of calculated annular volume to 300'.

- b) Production:

- i) Lead Cement: 230 sx of CBM Light Weight Cement with 10 pps Gilsonite and 1/4 pps celloflake mixed at 10.5 ppg and 4.14 ft³/sk.

- ii) Tail Cement: 210 sx of Class G (or equivalent) with 10% Cal-Seal, 1/4 pps celloflake and dispersant mixed at 14.2 ppg and 1.62 ft³/sk.

- iii) The Production Casing will be cemented using 2 (lead and tail) cement slurries. The lead cement (filler grade) volume will be calculated from 500' above the Upper Ferron Sandstone to surface. The Tail Cement will be calculated from TD to 500' above the Upper Ferron Sandstone as indicated on the formation tops table.

- (1) Slurry volume is 1,290 ft³, 200% excess of calculated annular volume to 3,683'.

- c) Slurry designs may change based upon actual conditions. Final cement volumes will be determined from caliper logs plus 100%.

5) Logging Program

- a) Mud Logger: The mud logger will come on at 300' and will remain on the hole until TD. The mud will be logged in 10' intervals.
- b) Open Hole Logs as follows: Run Array Induction (if wet), compensated neutron, density, GR, caliper, SP (if wet) and Pe fr/TD to the bottom of the surface csg.

6) Formation Tops:

Formation	Sub-Sea	Well Depth
Top Upper Ferron Sand	3,330	3,480
Top of Ferron Coal Zone	3,315	3,495
Top of Lower Ferron Sand	3,160	3,650
TOTAL DEPTH		3,950

- a) No known oil zones will be penetrated.

- b) Gas bearing sandstones and coals will be penetrated from 3,218' to 3,383'.

EXHIBIT E

- c) No known water zones will be penetrated. The gas bearing sandstones and coals may contain in-situ water.
- d) No known mineral zones will be penetrated.
- e) Any prospectively valuable minerals and all fresh water zones encountered during drilling will be recorded and cased and cemented. If possible, water flow rates will be measure and samples will be taken and analyzed with the results being submitted to the State of Utah.

7) Company Personnel:

Name	Title	Office Phone	Home Phone
Greg Vick	Drilling Engineer	505-566-7946	505-320-7274
Jerry Lacy	Drilling Super.	505-566-7914	505-320-6543
Dennis Elrod	Drilling Foreman	505-566-7907	505-486-6460
Joshua Stark	Project Geologist	817-885-2240	817-565-7158
Jerry Stadulis	Reservoir Engineer	817-855-2338	817-480-4056

BOP SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

TESTING PROCEDURE

1. Test BOP after installation:

Pressure test BOP to 200-300
psig (low pressure) for 10 min.

Test BOP to Working Press or
to 70% internal yield of surf csg
(10 min) or which ever is less.


2. Test operation of (both) rams on every trip.

3. Check and record Accumulator pressure on every tour.

4. Re-pressure test BOP stack after changing out rams.

5. Have kelly cock valve with handle available.


6. Have safety valve and subs to fit all sizes of drill string on the rig floor and ready to go.



CHOKES MANIFOLD SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

1. Stake all lines from choke manifold to pit.
2. Pressure test choke manifold after installation.
3. Pressure test manifold at the same time with the BOP Stack. Test manifold to the same test pressures.

TESTING PROCEDURE



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 07/31/2006

API NO. ASSIGNED: 43-015-30699

WELL NAME: ST OF UT 17-28-12 X
OPERATOR: XTO ENERGY INC (N2615)
CONTACT: KYLA VAUGHAN

PHONE NUMBER: 505-324-1090

PROPOSED LOCATION:

RIG SKID

SWNW 28 170S 080E

SURFACE: 1332 FNL 0582 FWL

BOTTOM: 1332 FNL 0582 FWL

COUNTY: EMERY

LATITUDE: 39.31844 LONGITUDE: -111.0361

UTM SURF EASTINGS: 496889 NORTHINGS: 4351907

FIELD NAME: BUZZARD BENCH (132)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DKD	8/15/06
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-48218

SURFACE OWNER: 3 - State

PROPOSED FORMATION: FRSD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:


☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 104312762)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. MUNICIPAL)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

☐ R649-2-3.
Unit: HUNTINGTON CBM
☐ R649-3-2. General
Siting: 460' From Qtr/Qtr & 920' Between Wells
☐ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 245-2
Eff Date: 4-25-01
Siting: 460' fr u bary ? unknown. Tract 5
☐ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: (No S.O.B. NEEDED)




OPERATOR: XTO ENERGY INC (N2615)

SEC: 28 T.17S R. 8E

FIELD: BUZZARD BENCH (132)

COUNTY: EMERY

CAUSE: 245-2 / 4-25-2001



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 03-AUGUST-2006

08-06 XTO St of Ut 17-8-2 12X

Casing Schematic

Surface

8-5/8"
MW 8.4
Frac 19.3

TOC @
0.
TOC @
0.
Surface
300. MD

✓ w/ 118% washout

BHP

$$(.052)(3950)(8.6) = 1766$$

Gw

$$(.12)(3950) = 474$$

$$MASP = 1292$$

BOPE - 2,000 ✓

Surf csg - 2950
70% = 2065

Mat pressure @ Surf csg shoe ~~1328~~ 1328

Test To ~~1328~~ 1328 psi ✓
(± 1200 psi sur. l. plus.)

✓ w/ 20% washout

2844 TOC Tail

3480 Upper Perm S.S.

✓ Adequate
DUCD

8/15/06

5-1/2"
MW 8.6

Production
3950. MD

Well name:	08-06 XTO St of Ut 17-8-28-12X	
Operator:	XTO Energy, Inc.	Project ID:
String type:	Surface	43-015-30699
Location:	Emery County	

Design parameters:

Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 79 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 264 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 262 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 3,950 ft
Next mud weight: 8.600 ppg
Next setting BHP: 1,765 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	14.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	1370	10.476	300	2950	9.83	6	244	38.82 J

Prepared Clinton Dworshak
by: Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: August 8, 2006
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	08-06 XTO St of Ut 17-8-28-12X	
Operator:	XTO Energy, Inc.	Project ID:
String type:	Production	43-015-30699
Location:	Emery County	

Design parameters:

Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 130 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 396 psi
Internal gradient: 0.346 psi/ft
Calculated BHP 1,765 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 3,436 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	3950	5.5	15.50	J-55	ST&C	3950	3950	4.825	123.8
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1765	4040	2.289	1765	4810	2.73	53	202	3.79 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: August 8, 2006
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 3950 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

August 16, 2006

XTO Energy, Inc.
2700 Farmington Ave, Bldg K, Ste. 1
Farmington, NM 87401


Re: State of Utah 17-8-28-12X Well, 1332' FNL, 582' FWL, SW NW, Sec. 28,
T. 17 South, R. 8 East, Emery County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-015-30699.

Sincerely,


for Gil Hunt
Associate Director

pab
Enclosures

cc: Emery County Assessor
SITLA

Operator: XTO Energy, Inc.
Well Name & Number State of Utah 17-8-28-12X
API Number: 43-015-30699
Lease: ML-48218

Location: SW NW Sec. 28 T. 17 South R. 8 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO: ML-48218	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> RIGSKID		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: N/A Huntington CBM	
2. NAME OF OPERATOR: XTO Energy, Inc.		9. WELL NAME and NUMBER: State of Utah 17-8-28-12X	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. B CITY Farmington STATE NM ZIP 87401		10. FIELD AND POOL, OR WILDCAT: Ferron Sandstone Buzzard	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1332' FNL x 582' FWL in Sec 28, T17S, R8E AT PROPOSED PRODUCING ZONE: same 4351007Y - 111.036083		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 3.75 miles West of Huntington, Utah		12. COUNTY: Emery	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1475'	16. NUMBER OF ACRES IN LEASE: 1800.92	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) None	19. PROPOSED DEPTH: 3,950	20. BOND DESCRIPTION: UTB-000138	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6791' Ground Elevation	22. APPROXIMATE DATE WORK WILL START: 9/15/2006	23. ESTIMATED DURATION: 2 weeks	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12.25"	8.625"	J-55	24#	300	Class G	+/- 210 sxs	1.18 ft3/sx 15.7 ppg
7.875"	5.5"	J-55	15.5#	3,950	CBM light wt - lead	+/- 230 sx	4.15 ft3/sx 10.5 ppg
					Class G	+/- 210 sx	1.62 ft3/sx 14.2 ppg

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Kyla Vaughan TITLE Regulatory Compliance Tech

SIGNATURE Kyla Vaughan DATE 7/26/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-015-30699

(11/2001)


Approved by the
Utah Division of
Oil, Gas and Mining

Date: 08-16-06
By: [Signature]

RECEIVED
JUL 31 2006
DIV. OF OIL, GAS & MINING

Range 8 East

Township 17 South



Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

NOTE:

UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG	
39°19'06.739" N	111°02'10.369" W

Location:

THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:

THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:

THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:


BASIS OF ELEVATION OF 6495' BEING AT THE SOUTHEAST SECTION CORNER OF SECTION 20, TOWNSHIP 17 SOUTH, RANGE 8 EAST, SALT LAKE BASE & MERIDIAN, AS SHOWN ON THE RED POINT QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:

PROPOSED DRILL HOLE LOCATED IN THE SW 1/4 NW 1/4 OF SECTION 28; BEING 1331.55' FROM THE NORTH LINE AND 582.01' FROM THE WEST LINE OF SECTION 28, T17S, R8E, SALT LAKE BASE AND MERIDIAN.

Surveyor's Certificate:

I, ALBERT J. SPENSKO, A REGISTERED PROFESSIONAL LAND SURVEYOR, HOLDING CERTIFICATE 146652 STATE OF UTAH, DO HEREBY CERTIFY THAT THE INFORMATION ON THIS DRAWING IS A TRUE AND ACCURATE SURVEY BASED ON DATA OF RECORD AND WAS CONDUCTED UNDER MY PERSONAL DIRECTION AND SUPERVISION AS SHOWN HEREON.



GRAPHIC SCALE



TALON RESOURCES, INC.

195 N. 100 W., P.O. Box 1230

Huntington, Utah 84528

Phone (435)687-5310 Fax (435)687-5311

E-Mail talon@etv.net



State of Utah #17-8-28-12
Section 28, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-1	Date: 02/22/06
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 2059

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1332' FNL & 582' FWL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 08E

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 9/15/2006	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to change the casing & cement program per attached.

RECEIVED

SEP 18 2006

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) HOLLY C. PERKINS

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE

DATE 9/12/2006

(This space for State use only)

(5/2000)

(See Instructions on Reverse Side)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS AND MINING

DATE: 9/25/06
Signature: [Signature]



Well Name: State of Utah 17-8-28-12X
 Location: 1332' FNL & 582' FWL, Sec. 28, T17S, R08E
 County: Emery County
 State: Utah

Upper Ferron SS (est): 3480

Surface Casing Detail

Type:	Type V cement (or equivalent) containing 1% CaCl, 1/4 pps Flocele and 10% Cal_Seal			
Percent Excess:	200.00%	Lead Density (ppg):	14.20	
Calc'd Volume (Bbls):	69.0	Lead Yield (cuft/sk):	1.61	
Calc'd Volume (cuft):	387.5			
Lead Volume (sxs):	240.7			

Production Casing Detail

String	Casing Type	Weight	OD	ID	Depth	Open Hole
Surface	8.625 J-55 24	24.00	8 5/8	8.097	300.0	12 1/4
Longstring	5.5 J-55 15.5	15.50	5 1/2	4.950	3950.0	7 7/8

Float Equipment

Cement Tops

Desc.	Depth	Hyd. Head	Stage 1 Top:	2338
Float Insert	3905.0	Lead: 459.46	Stage 2 Top:	3180
Float Shoe	3950.0	Tail: 540.54		

Spacer Description

Type:	10 bbls chem wash + 5 bbls scavenger slurry			
Volume (bbls):	15	Density (ppg):	9.00	

Lead Description

Type:	CBM Light Weight Cement with 10 pps Gilsonite and 1/4 pps celloflake				
Percent Excess:	40.00%	Lead Density (ppg):	10.50		
Calc'd Volume (Bbls):	36.4	Lead Yield (cuft/sk):	4.14		
Calc'd Volume (cuft):	204.2	Lead Mix Water (gal/sk):	27.53		
Lead Volume (sxs):	49.0	Mix Water (bbls):	32.1		


Tail Description

Type:	CBM Light Weight Cement with 10 pps Gilsonite and 1/4 pps celloflake				
Percent Excess:	40.00%	Tail Density (ppg):	13.5		
Calc'd Volume (Bbls):	34.33419	Tail Yield (cuft/sk):	1.81		
Calc'd Volume (cuft):	192.7804	Tail Mix Water (gal/sk):	8.84		
Tail Volume (sxs):	107	Mix Water (bbls):	22.5		

Displacement Description

Type:	Fresh Water				
Calc'd Volume (Bbls):	94.00	Density (ppg):	8.40		

Casing Schematic



Well name:

09-06 XTO St of Ut 17-8-28-12Xrev.

Operator: **XTO Energy, Inc.**

String type: Surface

Project ID:

43-015-30699

Location: Emery County

Design parameters:**Collapse**

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 79 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 264 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 262 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 3,950 ft
Next mud weight: 8.600 ppg
Next setting BHP: 1,765 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure: 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	107.1
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	1370	10.479 ✓	300	2950	9.83 ✓	6	244	38.83 J ✓

Prepared Dustin K. Doucet
by: Div of Oil, Gas & Minerals

Phone: 801-538-5281
FAX: 801-359-3940

Date: September 25, 2006
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

09-06 XTO St of Ut 17-8-28-12Xrev.

Operator: **XTO Energy, Inc.**

String type: Production

Project ID:

43-015-30699

Location: Emery County

Design parameters:**Collapse**Mud weight: 8.600 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 130 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 2,546 ft

BurstMax anticipated surface
pressure: 896 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 1,765 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 3,436 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	3950	5.5	15.50	J-55	ST&C	3950	3950	4.825	527.9
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1765	4040	2.289 ✓	1765	4810	2.73 ✓	53	202	3.79 J ✓

Prepared Dustin K. Doucet
by: Div of Oil, Gas & MineralsPhone: 801-538-5281
FAX: 801-359-3940Date: September 25, 2006
Salt Lake City, Utah**Remarks:**Collapse is based on a vertical depth of 3950 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes.
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECEIVED

FORM 6

OCT 02 2006

ENTITY ACTION FORM

DIV. OF OIL, GAS & MINING

Operator: XTO ENERGY INC.
Address: 2700 FARMINGTON AVE K #1
city FARMINGTON
state NM zip 87401

Operator Account Number: N 2615

Phone Number: (505) 324-1090

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301530699	STATE OF UTAH 17-8-28-12X		SWNW	28	17S	08E	EMERY
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	15691	9/14/2006		10/5/06		
Comments: FRSD							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

HOLLY C. PERKINS

Name (Please Print)

Signature

Regulatory Compliance Tech

Title

9/25/2006

Date

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Bldg K1 CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1332' FNL & 582' FWL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E S

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-48218

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
STATE OF UTAH 17-8-28-12X

9. API NUMBER:
4301530699

10. FIELD AND POOL, OR WILDCAT:
FERRON SANDSTONE

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 9/17/2006	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. drilled 17-12" hole on 9/14/06 & set 13 3/8", 48#, conductor casing @ 29'. Cmt'd w/70 sx of Redi-Mix. Drilled 12-1/4" hole to 315'. Set 8 5/8", 24#, J55 casing @ 315'. Cmt'd w/240 sx Type V cmt.

Drilling ahead . . .

RECEIVED

OCT 02 2006

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) HOLLY C. PERKINS

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE

DATE 9/22/2006

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48218
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1332' FNL & 582' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 18 17S 8E S		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-28-12X
PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530699
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 10/26/2006	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached is the monthly activity report from 9/30/2006 to 10/26/2006 FOR THIS WELL

NAME (PLEASE PRINT) HOLLY C. PERKINS	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE <i>Holly C. Perkins</i>	DATE 10/26/2006

(This space for State use only)

RECEIVED

OCT 31 2006

DIV. OF OIL, GAS & MINING

EMERY**STATE OF UTAH 17-8-28-12X**

LOCATION : SYNW, Sec 28, T17S, R8E
CONTRACTOR: Stewart Brothers, 48
WI %:
AFE#: 651982
APH#: 43015306990000
DATE FIRST RPT: 9/14/2006

DATE: 9/14/2006
OPERATION: Rig Repair
DFS: -0.6 Footage Made:
MW: VISC:
WOB: RPM:
DMC: CMC: DWC: 12,743.00 CWC: 12,743.00
TIME DIST: (12.00) Move on location. (12.00) Wait on parts for rig repair.

DATE: 9/15/2006
OPERATION: Cleaning Boulder to set conductor
DFS: 0.4 Footage Made: 29 Measured Depth: 29
MW: VISC:
WOB: RPM:
DMC: CMC: DWC: 8,673.00 CWC: 21,416.00
TIME DIST: (14.50) Rig Repair. (7.00) Drilling Conductor, 0' to 29'. (2.50) Cleaning conductor hole of boulders.

DATE: 9/16/2006
OPERATION: Drilling Surface
DFS: 1.4 Footage Made: 41 Measured Depth: 70
MW: VISC:
WOB: RPM:
DMC: CMC: DWC: 23,360.00 CWC: 44,776.00
TIME DIST: (1.00) Finish cleaning hole. (2.00) Run Conductor. (2.75) Cementing conductor casing using 70 bags of red-mix. (2.25) Waiting on cement, shift change safety meeting. (4.00) Digging cellar. (4.00) Rig up rotating head. (1.75) Re-rig up rig after digging cellar. (0.25) Shift change safety meeting. (1.50) Finish rigging up flowline. (0.50) T.I.H., tag cement at 21'. (1.00) Drilling cement from 21' to 29'. (3.00) Drilling from 29' to 70'.

DATE: 9/17/2006
OPERATION: Drilling Surface
DFS: 2.4 Footage Made: 244 Measured Depth: 314
MW: VISC:
WOB: RPM:
DMC: CMC: DWC: 11,486.00 CWC: 56,262.00
TIME DIST: (4.00) Drilling from 70' to 100'. (0.25) Survey at 100' @ 1/4 degree. (1.50) Drilling from 100' to 126'. (0.25) Shift change safety meeting. (4.00) Drilling from 126' to 200'. (0.25) Survey at 200' @ 1 degree. (4.75) Drilling from 200' to 265'. (2.75) Rig repair, repair kelly hose. (0.25) Shift change safety meeting. (4.75) Drilling from 265' to 302'. (0.25) Survey at 300' @ 2 degrees. (1.00) Drilling from 302' to 314'.

DATE: 9/18/2006
OPERATION: W.O.C.
DFS: 3.4 Footage Made: 9 Measured Depth: 323
MW: VISC:
WOB: RPM:
DMC: CMC: DWC: 38,226.00 CWC: 94,488.00
TIME DIST: (2.25) Drilling from 314' to 323'. (0.25) Survey at 320' @ 1 3/4 degree. (0.50) Circulate hole. (1.25) Trip out of hole laying down to run surface casing. (0.25) Start running surface casing, hit obstruction at 30', lay down casing prepare to wash down. (1.25) Wash and ream to bottom. (0.25) Shift change safety meeting. (6.50) Run 8 5/8" 24# surface casing, land at 315'. (0.50) Rig up Halliburton and have safety meeting. (1.00) Pump cement for surface casing, circulate approx. 20 bbls cement to surface. (10.00) Wait on Cement, after 4 hours rig down circulating head, cut casing and weld on well head, pressure test B.O.P.'s and casing.

DATE: 9/19/2006
OPERATION: Drilling
DFS: 4.4 Footage Made: 119 Measured Depth: 442

MW:
WOB: 10
DMC:
TIME DIST:

VISC:
RPM: 80
CMC:

DWC: 14,378.00
CWC: 108,866.00

(1.00) Finish NU/B.O.P.. (3.00) Pressure test rams, (blinds and pipe) 300 psi low-1000 psi high, choke manifold, 300 psi low-1000 psi high, Casing 300 psi low-1000 psi high for 30 minutes. (1.75) NU rotating head and flowline. (0.25) Shift change safety meeting. (4.50) Change oils and lubricate rig. (1.00) Trip in hole and tag cement at 260'. (4.00) Drill float, cement and shoe. (2.25) Drilling from 323' to 370'. (0.25) Shift change safety meeting. (3.25) Drilling from 370' to 403'. (0.25) Survey at 400' @ 2 1/2 degrees. (2.50) Drilling from 403' to 442'.

DATE: 9/20/2006
OPERATION: Drilling
DFS: 5.4
MW:
WOB: 7
DMC:

Footage Made: 358
VISC:
RPM: 100
CMC:

Measured Depth: 800
DWC: 14,212.00
CWC: 123,078.00

TIME DIST: (3.50) Drilling from 442' to 502'. (0.25) Survey at 500' @ 2 degrees. (0.50) Drilling from 502' to 522'. (1.50) Work on drive bushing. (0.25) Shift change safety meeting. (3.00) Drilling from 522' to 582'. (0.50) Survey at 582' @ 3 degrees. (1.50) Drilling from 582' to 622'. (0.25) Survey at 622' @ 3 degrees. (1.75) Drilling from 622' to 663'. (0.25) Survey at 663' @ 2 3/4 degree. (1.75) Drilling from 663' to 703'. (0.50) Survey at 703' @ 2 3/4 degree. (2.00) Drilling from 703' to 743'. (0.50) Shift change safety meeting. (0.25) Survey at 743' @ 2 1/4 degree. (5.75) Drilling from 743' to 800'.

DATE: 9/21/2006
OPERATION: Tripping for Motor
DFS: 6.4
MW:
WOB: 5
DMC:

Footage Made: 143
VISC:
RPM: 100
CMC:

Measured Depth: 943
DWC: 15,084.00
CWC: 138,162.00

TIME DIST: (0.25) Operate pipe rams. (4.50) Drilling from 800' to 843'. (0.25) Survey at 843' @ 2 1/4 degree. (0.75) Work on Kelly drive bushing. (0.25) Shift change safety meeting. (11.75) Drilling from 843' to 878'. (0.25) Shift change safety meeting. (3.00) Drilling from 878' to 943'. (0.50) Survey at 940' @ 3 1/2 degrees. (2.50) Trip out of hole to pick up motor and new bit.

DATE: 9/22/2006
OPERATION: Drilling
DFS: 7.4
MW:
WOB: 2
DMC:

Footage Made: 250
VISC:
RPM: 110
CMC:

Measured Depth: 1,193
DWC: 32,384.00
CWC: 170,546.00

TIME DIST: (2.00) Trip in hole with new bit and motor. (3.75) Drilling from 943' to 1011'. (0.25) Shift change safety meeting. (0.25) Survey at 1011' @ 3 degrees. (2.75) Drilling from 1011' to 1071'. (0.50) Survey at 1051' @ 3 degrees. (3.00) Drilling from 1071' to 1111'. (0.50) Survey at 1091' @ 3 degrees. (4.75) Drilling from 1111' to 1161'. (0.25) Shift change safety meeting. (2.00) Drilling from 1161' to 1171'. (0.25) Survey at 1171' @ 2 3/4 degree. (3.75) Drilling from 1171' to 1193'.

DATE: 9/23/2006
OPERATION: Tripping in the hole
DFS: 8.4
MW:
WOB: 2
DMC:

Footage Made: 111
VISC:
RPM: 110
CMC:

Measured Depth: 1,304
DWC: 20,644.00
CWC: 191,190.00

TIME DIST: (0.25) Operate pipe rams. (1.75) Drilling from 1193' to 1211'. (0.25) Survey at 1211' @ 2 degrees. (3.50) Drilling from 1211' to 1252'. (0.25) Shift change safety meeting. (1.75) Drilling from 1252' to 1272'. (0.50) Survey at 1252' @ 3 degrees. (4.75) Drilling from 1272' to 1302'. (0.50) Survey at 1292' @ 3 degrees. (0.50) Drilling from 1302' to 1304' lost air pressure.. (3.75) T.O.H. to inspect drill string. (0.25) Shift change safety meeting. (3.00) Pin sheared between 1st and 2nd collar, pick up spear and trip in to fish remaining B.H.A.. (2.50) Trip out of hole with fish.. (0.50) Pick up new motor and B.H.A. trip in hole.

DATE: 9/24/2006
OPERATION: Drilling @ 1592'

DFS: 9.4 **Footage Made:** 290 **Measured Depth:** 1,594
MW: **VISC:**
WOB: 2 **RPM:** 110 **DWC:** 21,894.00 **CWC:** 213,084.00
DMC: **CMC:**
TIME DIST: (1.00) Trip in Hole. (1.00) Work on Rotating Head. (3.00) Drilling. (0.25) WLS @ 1333' was 3 degree. (0.50) Work on Rotating Head. (0.25) Safety Meeting. (2.25) Drilling. (0.25) WLS @ 1393' was 2.75 degree. (1.50) Drilling. (0.25) WLS @ 1433' was 2.5 degree. (1.75) Drilling. (0.50) WLS @ 1472.0 was 1.75 degree. (2.00) Drilling. (0.25) WLS @ 1513.0 was 2.25 degree. (2.75) Drilling. (0.25) WLS @ 1554 was 3.0 degree. (0.25) Safety Meeting. (6.00) Drilling.

DATE: 9/25/2006
OPERATION: Waiting on Fishing Tools
DFS: 10.4 **Footage Made:** 101 **Measured Depth:** 1,695
MW: **VISC:**
WOB: 2 **RPM:** 110 **DWC:** 20,644.00 **CWC:** 233,728.00
DMC: **CMC:**
TIME DIST: (0.25) WLS @ 1594 was 1.5 degree. (0.25) Function Test pipe Rams. (3.75) Drilling. (0.25) WLS @ 1636' was 2.75 degree. (1.25) Drilling. (0.25) Safety Meeting. (3.50) Drilling. (0.25) WLS @ 1677' was 2.25. (1.50) Drilling, Twisted Off, Lost all Collor WL. (3.25) Trip Out, Twisted Off Pin on 4 3/4 Cross-over sub. (2.25) Pick up spear and Trip In Hole. (3.75) Spear Fish, POOH. (1.00) Lost Fish, TIH. (1.00) Fishing, Could get a hold on fish with spear and pull 5K over string wt. spear would pull out of fish.. (1.50) POOH, Walk on Overshot and Jars.

DATE: 9/26/2006
OPERATION: POOH with Fish
DFS: 11.4 **Footage Made:** 0 **Measured Depth:** 1,695
MW: **VISC:**
WOB: 2 **RPM:** 110 **DWC:** 25,860.30 **CWC:** 259,588.30
DMC: **CMC:**
TIME DIST: (1.50) POOH, With Spear, Recovered 2 DC'S. (8.50) Wait On Fishing Tools. (7.75) Pick up 6 dc's, Jars, Overshot and Trip In Hole. (0.25) Safety Meeting. (1.00) Fishing. (5.00) POOH with Fish.

DATE: 9/27/2006
OPERATION: Changing over to mud drill
DFS: 12.4 **Footage Made:** 0 **Measured Depth:** 1,695
MW: **VISC:**
WOB: **RPM:** **DWC:** 29,881.77 **CWC:** 289,470.07
DMC: **CMC:**
TIME DIST: (1.00) POOH, NO FISH. (6.25) Pick up Skirted Mill, 6 dcs and Trip In Hole. (2.00) Establish Mist, Mill on Fish, Milled 8" over fish, excessive torque and sticky.. (4.75) POOH With Mill, Skirt on Mill was flaired out and cracked, Inner mill was left in hole. (10.00) Release Air Package and Fisherman, Rig Down Air Compressors, Truck will be here at daylight to move compressors and set in Steel Mud Pits.

DATE: 9/28/2006
OPERATION: Tripping In Hole to Dress Plug
DFS: 13.4 **Footage Made:** 0 **Measured Depth:** 1,695
MW: **VISC:**
WOB: **RPM:** **DWC:** 41,812.03 **CWC:** 331,282.10
DMC: **CMC:**
TIME DIST: (4.00) Set out Air Package, Set in Steel Pits. (2.00) Trip In Hole Open Ended. (4.00) Rig Up Steel Pits, Fill with Mud. (2.75) Load Hole, Circulate and Condition Mud. (0.50) Rig Up Halliburton and Spot Cement Plug. (2.75) POOH. (7.00) WOC. (1.00) Pick up BHA to Dress Plug.

DATE: 9/29/2006
OPERATION: Waiting On #2 Pump, Should Be Here By Daylight
DFS: 14.4 **Footage Made:** 0 **Measured Depth:** 1,695
MW: 8.7 **VISC:** 45
WOB: **RPM:** **DWC:** 74,934.43 **CWC:** 406,216.53
DMC: **CMC:**
TIME DIST: (4.50) Trip In Hole, Tag cement @ 1231'. (1.50) Dress Cement to 1351', Still Very Soft. (7.00) WOC. (0.50) Dress Cement to 1365', Good, Hard Cement. (2.50) POOH. (4.00) Pick Up BHA and Trip In Hole. (4.00) Wait On #2 Pump.

DATE: 9/30/2006
OPERATION: Slide Drilling
DFS: 15.4 **Footage Made:** 8 **Measured Depth:** 1,295
MW: 8.5 **VISC:** 40
WOB: 0 **RPM:** 0
DMC: **CMC:** **DWC:** 25,032.00 **CWC:** 431,248.53
TIME DIST: (2.00) Wait on #2 Pump. (3.75) Install and Rig Up #2 Pump. (0.25) Safety Meeting. (9.50) Install #2 Pump. (2.25) Trip In Hole. (0.25) Safety Meeting. (6.00) Slide Drilling.

DATE: 10/1/2006
OPERATION: Slide Drilling
DFS: 16.4 **Footage Made:** 25 **Measured Depth:** 1,320
MW: 8.4 **VISC:** 35
WOB: 0 **RPM:** 0
DMC: **CMC:** **DWC:** 26,908.28 **CWC:** 458,156.81
TIME DIST: (1.00) Work on #1 Pump. (4.75) Slide 1295' to 1301'. (0.25) Safety Meeting. (5.00) Slide 1301' to 1305'. (0.50) Work on Driveline. (6.25) Slide 1305' to 1313'. (0.25) Safety Meeting. (2.00) Slide 1313' to 1315'. (0.75) Work on #1 Pump. (1.25) Slide 1315' to 1317'. (1.00) Work on #1 Pump. (1.00) Slide 1317' to 1320'.

DATE: 10/2/2006
OPERATION: Slide Drilling
DFS: 17.4 **Footage Made:** 10 **Measured Depth:** 1,330
MW: 8.5 **VISC:** 34
WOB: 2 **RPM:** 0
DMC: **CMC:** **DWC:** 23,080.00 **CWC:** 481,236.81
TIME DIST: (0.25) Function Test Pipe Rams. (4.00) Slide Drig 1320 to 1325'. (1.50) POOH to DC'S. (0.25) Safety Meeting. (11.75) Rig Repair, Pump Clutch Drive. (0.25) safety Meeting. (1.00) Rig Repair. (4.00) Trip In Hole, Orient Tool Face. (1.00) Slide Drig 1325' to 1330'.

DATE: 10/3/2006
OPERATION: Drilling @ 1416'
DFS: 18.4 **Footage Made:** 86 **Measured Depth:** 1,416
MW: 8.6 **VISC:** 35
WOB: 8 **RPM:** 50
DMC: **CMC:** **DWC:** 22,498.00 **CWC:** 503,734.81
TIME DIST: (5.00) Slide 1330 to 1365'. (2.50) Rotate 1365' to 1377'. (1.00) Condition Mud. (8.50) Rotate 1377' to 1411'. (4.00) Change out Swab and Liner in #1 Pump. (1.50) Condition Mud. (1.50) Rotate 1411' to 1416'.

DATE: 10/4/2006
OPERATION: Drilling @ 1597'
DFS: 19.4 **Footage Made:** 181 **Measured Depth:** 1,597
MW: 8.6 **VISC:** 35
WOB: 15 **RPM:** 50
DMC: **CMC:** **DWC:** 22,768.00 **CWC:** 526,502.81
TIME DIST: (6.00) Drig 1460' to 1477'. (0.25) Safety Meeting. (11.50) Drig 1477' to 1577'. (0.25) Safety Meeting. (4.75) Work on #2 Pump. (1.25) Drig 1577' to 1597'.

DATE: 10/5/2006
OPERATION: Drilling @ 1670'
DFS: 20.4 **Footage Made:** 72 **Measured Depth:** 1,669
MW: 8.6 **VISC:** 36
WOB: 8 **RPM:** 45
DMC: **CMC:** **DWC:** 23,188.00 **CWC:** 549,690.81
TIME DIST: (2.75) Drig 1597' to 1625'. (0.25) Circulate. (3.00) POOH. Lay Down Directional Tools. (5.00) Change Oil in DW, Work on Cathead. (4.00) Pick Up PDC Bk, DC'S. and TIH. (2.75) Drig 1625' to 1645'. (0.25) Safety Meeting, Function Test Pipe Rams. (6.00) Drig. 1645 to 1669'.

DATE: 10/6/2006
OPERATION: Mix Mud and LCM
DFS: 21.4 **Footage Made:** 294 **Measured Depth:** 1,963
MW: 8.8 **VISC:** 33
WOB: 12 **RPM:** 45
DMC: **CMC:** **DWC:** 21,890.00 **CWC:** 571,580.81

TIME DIST: (2.50) Drig 1689' to 1689'. (0.25) WLS @ 1686' was 3 degree. (2.25) Drig 1686' to 1746'. (0.25) WLS @ 1740' was 2 degree. (0.50) Drig 1746' to 1766'. (0.25) Function Test Pipe Rams, and Hold Safety Meeting. (2.50) Drig 1766 to 1826'. (0.25) WLS @ 1800 was 1.75 degree. (0.75) Work on Pump. (9.50) Drig 1826' to 1963'. (2.00) Work on Pump. (1.00) Pull 7 Stands off Bottom. (2.00) Mix Mud and LCM.

DATE: 10/7/2006

OPERATION: Waiting on Air Package

DFS: 22.4 **Footage Made:** 0 **Measured Depth:** 1,963

MW: 8.5 **VISC:** 50

WOB: 12 **RPM:** 45

DMC: **CMC:** **DWC:** 13,890.00 **CWC:** 585,470.81

TIME DIST: (5.75) Mix and Pump 200 bbls Mud, 50 vis, 10 % LCM. (0.25) Safety Meeting. (3.00) Mix and Pump 100 Bbls Mud, 50 vis and 15% LCM. (2.50) Out of Water, Out of Mud, Pull up into Csg. (12.50) Wait On Air Package, Will Be Here Before Noon.

DATE: 10/8/2006

OPERATION: Rig Repair, DW Engine

DFS: 23.4 **Footage Made:** 112 **Measured Depth:** 2,075

MW: **VISC:**

WOB: 10 **RPM:** 65

DMC: **CMC:** **DWC:** 27,525.00 **CWC:** 612,995.81

TIME DIST: (5.75) Wait on Air Package. (0.25) Safety Meeting. (4.00) Set in and Rig up Air Compressors. (1.00) Try to Blow thru BHA, Motor Plugged. (1.50) POOH, Lay down Motor. (3.25) Trip In Hole. (1.25) Unload Hole, Clean Out 70' To Bottom. (0.75) Mist Drill 1963' to 1985'. (0.25) Safety Meeting. (3.50) Mist Drig 1985' to 2075'. (2.50) Drawworks Engine Locked Up, Wait on Engine From Grants.

DATE: 10/9/2006

OPERATION: Replace DW Engine

DFS: 24.4 **Footage Made:** 0 **Measured Depth:** 2,075

MW: **VISC:**

WOB: 10 **RPM:** 65

DMC: **CMC:** **DWC:** 7,900.00 **CWC:** 620,895.81

TIME DIST: (14.00) Wait on Drawworks Engine. (10.00) Install New DW Engine.

DATE: 10/10/2006

OPERATION: Mist Drilling @ 2615'

DFS: 25.4 **Footage Made:** 540 **Measured Depth:** 2,615

MW: **VISC:**

WOB: 15 **RPM:** 75

DMC: **CMC:** **DWC:** 15,100.00 **CWC:** 635,995.81

TIME DIST: (0.50) Rig Repair. (5.25) Drig 2075' to 2187'. (0.25) Safety Meeting. (0.25) Drig 2187' to 2195'. (0.25) WLS @ 2195' was 1.75 degree. (5.25) Drig 2195' to 2395'. (0.25) WLS @ 2395 was 2.0 degree. (5.75) Drig 2395' to 2487'. (0.25) Safety Meeting. (6.00) Drig 2487' to 2615'.

DATE: 10/11/2006

OPERATION: Mist Drilling @ 3076'

DFS: 26.4 **Footage Made:** 461 **Measured Depth:** 3,076

MW: **VISC:**

WOB: 8 **RPM:** 80

DMC: **CMC:** **DWC:** 19,300.00 **CWC:** 655,295.81

TIME DIST: (0.25) Function Test Pipe Rams. (3.00) Drig 2615' to 2695'. (0.25) WLS @ 2695' was 4.0 degree. (2.50) Drig 2695' to 2715'. (0.25) Safety Meeting. (1.50) Drig 2715' to 2735'. (0.50) WLS @ 2735' was 3.0 degree. (3.00) Drig 2735' to 2795'. (0.50) WLS @ 2795' was 2.50 degree. (4.25) Drig 2795' to 2935'. (0.75) WLS @ 2935' was 4.5 degree. (1.00) Drig 2935' to 2955'. (0.25) Safety Meeting. (3.00) Drig 2955' to 3015'. (0.50) WLS @ 3015' was 2.75 degree. (2.50) Drig 3015' to 3076'.

DATE: 10/12/2006

OPERATION: Mist Drilling @ 3324'

DFS: 27.4 **Footage Made:** 248 **Measured Depth:** 3,324

MW: **VISC:**

WOB: 6 **RPM:** 80

DMC: **CMC:** **DWC:** 16,369.00 **CWC:** 671,664.81

TIME DIST: (0.25) Function Test Pipe Rams. (0.75) Drig 3076' to 3097'. (2.25) WLS @3097.Missrun, Fix Wireline and RRun Survey, 3 degree. (2.50) Drig 3097' to 3136'. (0.25) Safety Meeting. (0.50) Drig 3136' to 3166'. (0.50) WLS @ 3166' was 3.5 degree. (3.50) Drig 3166' to 3216'. (0.75) Circ. and WLS @ 3216' was 3.5 degree. (3.50) Drig 3216' to 3276'. (0.50) WLS @ 3276 was 4 degree. (2.50) Drig 3276' to 3307'. (0.25) Safety Meeting. (1.50) Drig 3307' to 3316'. (0.50) WLS @ 3316' was 3 degree. (4.00) Drig 3316 to 3324'.

DATE: 10/13/2006

OPERATION: Mist Drilling @ 3536'

DFS: 28.4 **Footage Made:** 192 **Measured Depth:** 3,516

MW: **VISC:**

WOB: 6 **RPM:** 80

DMC: **CMC:** **DWC:** 56,869.00 **CWC:** 728,533.81

TIME DIST: (0.25) Function test Pipe Rams. (2.50) Drig 3324' to 3373'. (0.25) WLS @ 3373' was 4.5 degree. (2.00) Drig 3373' to 3393'. (2.00) Replace Kelly Cable. (2.00) Drig 3393' to 3416'. (0.50) Circ and WLS @ 3416' was 3.25 degree. (1.00) Repair Kelly Bushings. (6.50) Drig 3416' to 3476'. (1.00) Circ and WLS @ 3476' was 3.75 degree. (6.00) Drig 3476' to 3516'.

DATE: 10/14/2006

OPERATION: Blow Hole @ 3820' T.D.

DFS: 29.4 **Footage Made:** 304 **Measured Depth:** 3,820

MW: **VISC:**

WOB: 6 **RPM:** 80

DMC: **CMC:** **DWC:** 164,522.00 **CWC:** 893,055.81

TIME DIST: (0.25) Function Test Pipe Rams. (2.75) Drig 3516' to 3536'. (0.50) WLS @ 3536' was 3.25 degree. (2.25) Drig 3536' to 3561'. (0.25) Safety Meeting. (5.00) Drig 3561' to 3656'. (0.50) WLS @ 3656' was 4 degree. (6.25) Drig 3656' to 3740'. (0.25) Safety Meeting. (5.25) Drig 3740' to 3820' TD. (0.75) Blow Hole Clean.

DATE: 10/15/2006

OPERATION: Rig Up Schlumberger

DFS: 30.4 **Footage Made:** 0 **Measured Depth:** 3,820

MW: **VISC:**

WOB: **RPM:**

DMC: **CMC:** **DWC:** 15,537.00 **CWC:** 908,592.81

TIME DIST: (0.50) Blow Hole. (5.50) Short Trip 20 Stands, Tight 1st 5 stands off bottom. (0.25) Safety Meeting. (2.00) TIH. (2.00) Wash 75' to Bottom (Hard Fill). (2.00) Blow Hole on Bottom. (2.00) Work 1st 5 Jts out of Hole, Tight. (3.75) Lay Down 50 Jts. (6.00) Stand Back Remaining DP and Lay Down BHA.

DATE: 10/16/2006

OPERATION: Wash Csg to Bottom @ 3647'

DFS: 31.4 **Footage Made:** 0 **Measured Depth:** 3,820

MW: **VISC:**

WOB: **RPM:**

DMC: **CMC:** **DWC:** 15,537.00 **CWC:** 924,129.81

TIME DIST: (4.50) Loggs Stopped @ 3278', Rig Down Loggers. (3.50) Trip in Hole With DP. (6.00) Lay Down D.P.. (8.00) Run 5 1/2 Csg. (2.00) Wash Csg to Bottom.

DATE: 10/17/2006

OPERATION: Rigging Down

DFS: 32.4 **Footage Made:** 0 **Measured Depth:** 3,820

MW: **VISC:**

WOB: **RPM:**

DMC: **CMC:** **DWC:** 48,503.75 **CWC:** 972,633.56

TIME DIST: (4.00) Wash Casing from 3647' to 3692'- Hole Sloughing and trying to Bridge Off. (2.00) Blow Hole, Still Very Tight, Try to go down, It Cuts Circ.. (2.00) Blow Hole, Spot and Rig up Halliburton. (2.00) Blow Hole, Wait On Surface Sweep and Fiber seal For pre-cement Sweep. (3.50) Mix Surface Sweep and Cement. (4.50) Nipple Down, Set Csg Slips and Cut Off Csg. (6.00) Rig Down.

Farmington Well Workover Report

STATE OF UTAH	Well # 17-08-28-12X	FERRON SANDSTON
---------------	---------------------	-----------------

Objective: Drill & Complete

First Report: 09/07/2006

AFE: 651982

9/7/06 Notified Dan Jarvis (DOGM, Salt Lake City, Utah) & Carol Daniels (DOGM, Salt Lake City, Utah) on 9/1/06 regarding pending construction. Built new loc, acc road & res pit. Lnd res pit. Notified Dan Jarvis (DOGM, Salt Lake City, Utah) & Carol Daniels (DOGM, Salt Lake City, Utah) on 9/1/06 regarding conductor csg. Susp rpts pending further activity.

Farmington Morning Report

Thursday, October 26, 2006

<u>Date</u>	<u>Description</u>	<u>Sales Volume</u>	<u>Comment</u>
10/24/06	El Paso	86,053 MCF	LP 135 psig
10/24/06	Western Gas	3,067 MCF	LP 282 psig
10/24/06	Williams	29,750 MCF	LP 119 psig
10/24/06	Durango	62,721 MCF	LP 311 psig
10/24/06	Raton	45,457 MCF	LP 1,192 psig
10/24/06	Utah	19,711 MCF	LP 499 psig
10/24/06	Fuel Estimated	17,222 MCF	
10/24/06	TOTAL	263,981MCF	

STATE OF UTAH	Well # 17-08- 28-12X	FERRON SANDSTON	Emery, UT
---------------	-------------------------	--------------------	-----------

Objective: Drill & Complete

Rig: Schlumberger

AFE: 650457

1st Rept: 09/07/2006

10/24/06 Cont rpt for AFE # 650457 to D & C Ferron Coal/sd. MIRU Schlumberger WL w/ mast. Run RST Sigma mode fr/3,623' - 3,023'. Run RST Carbon Oxygen IC mode fr/3,623' - 3,023' & GR/CCL/CBL fr/3,641' - 200' fr/surf. Log showed v. gd cmt bond fr/3,641' to 2,650', fr cmt fr/2,650' to 2,560' & pr cmt fr/2,560' to TOC @ 2,300'. LD logging tls. RDMO WL. Susp rpts to further activity.

DWC: \$10,000 CWC: \$10,500 DMC: \$0 CMC: \$0



TABULATION OF DEVIATION TESTS

XTO Energy Inc.

Depth	Degrees	Depth	Degrees	Depth	Degrees
1686'	3 °	3276'	4 °		°
1740'	2 °	3416'	3 ¼ °		°
1800'	1 ¾ °	3476'	3 ¼ °		°
2195'	1 ¼ °	3536'	3 ¼ °		°
2395'	2 °	3656'	4 °		°
2735'	3 °		°		°
2795'	2 ½ °		°		°
3156'	3 ½ °		°		°
3216'	3 ½ °		°		°

A F F I D A V I T

THIS IS TO CERTIFY that to the best of my knowledge the above survey details the deviation tests taken on XTO ENERGY INC'S

State of Utah 17-8-28-12X
in Section 28, T17S, R8E,
API # 43-015-30699
Emery County, Utah.

Signed

Printed Name

Title

Brent H. Martin

Brent H. Martin

Drilling Manager

RECEIVED

NOV 02 2006

DIV. OF OIL, GAS & MINING


THE STATE OF NEW MEXICO)

) SS.

COUNTY OF SAN JUAN)

BEFORE ME, the undersigned authority, on this day personally, Brent H. Martin, known to me to be Drilling Manager for XTO Energy Inc and to be the person whose name is subscribed to the above statement, who, being by me duly sworn on oath, states that he has knowledge of the facts stated herein and that said statement is true and correct.

SUBSCRIBED AND SWORN to before me, a Notary Public in and for said County and State this 30th day of October, 2006.



Wally C. Perkins

My Commission Expires:

9-1-2008



RECEIVED

NOV 20 2006

TABULATION OF DEVIATION TESTS

XTO Energy Inc.

DIV. OF OIL, GAS & MINING

Depth	Degrees	Depth	Degrees	Depth	Degrees	Depth	Degrees
200'	1 °	703'	2 ¾ °	1342'	2 ¾ °	2735'	3 °
263'	1 ¼ °	740'	2 ¼ °	1513'	2 ¼ °	2795'	2 ½ °
300'	2 °	840'	2 ¼ °	1554'	3 °	3156'	3 ½ °
323'	1 ¾ °	940'	3 ½ °	1594'	1 ½ °	3216'	3 ½ °
400'	2 ½ °	490'	3 ½ °	1686'	3 °	3276'	4 °
500'	2 °	1051'	3 °	1740'	2 °	3416'	3 ¼ °
582'	3 °	1178'	2 ¾ °	1800'	1 ¾ °	3476'	3 ¼ °
622'	6 °	1211'	2 °	2195'	1 ¼ °	3536'	3 ¼ °
663'	2 ¾ °	1272'	3 °	2395'	2 °	3656'	4 °

A F F I D A V I T

THIS IS TO CERTIFY that to the best of my knowledge the above survey details the deviation tests taken on XTO ENERGY INC'S

State of Utah 17-8-28-12X
in Section 28, T17S, R8E,
API # 43-015-30699
Emery County, Utah.

Signed

Printed Name

Title

Brent H. Martin

Drilling Manager

THE STATE OF NEW MEXICO)

) SS.

COUNTY OF SAN JUAN)


BEFORE ME, the undersigned authority, on this day personally, Brent H. Martin, known to me to be Drilling Manager for XTO Energy Inc and to be the person whose name is subscribed to the above statement, who, being by me duly sworn on oath, states that he has knowledge of the facts stated herein and that said statement is true and correct.

SUBSCRIBED AND SWORN to before me, a Notary Public in and for said County and

State this 10th day of November, 2006.

Notary Public

My Commission Expires:

9-1-2008

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48218
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington, Bldg K-1 CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1332' FNL & 582' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 28 17S 08E		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-28-12X
PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530699
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE
		COUNTY: EMERY
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: MONTHLY RPT
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 12/6/2006			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached is XTO Energy Inc.'s monthly report for the period of 10/27/06 to 12/6/06.

NAME (PLEASE PRINT) HOLLY C. PERKINS	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE _____	DATE 12/6/2006

(This space for State use only)

RECEIVED
DEC 13 2006

Farmington Well Workover Report

STATE OF UTAH	Well # 17-08-28-12X	FERRON SANDSTON
---------------	---------------------	-----------------

Objective: Drill & Complete

First Report: 09/07/2006

AFE: 650457

11/2/06 Cont rpt for AFE # 650457 to D & C Ferron Coal/sd. Fr/10-24-06 - 11-2-06. NU frac vlv. Set & fill 12 - 500bbl frac tanks w/FW. MIRU Big Red Hot Oil Service. PT csg, WH & frac valve to 4,000 psig for 30". Tstd OK. RDMO Big Red. MIRU Bran-Dex WL. RIH w/ 4" Slick Csg Gun. Perf L Ferron Coal w/3 JSPF fr/3,462' - 3,465' & 3,481' - 3,495'. (51 holes, 22.7 gm, .41" dia, 120 deg ph). All dpts correlated fr/Schlumberger RST/GR/CCL/CBL log ran on 10-23-06. POH & LD csg gun. RIH w/dump blr & dmpd 10 gals 28 % HCL @ 3,490'. POH & LD dump blr. RD Bran-Dex WLU. MIRU Halliburton frac crew. A L/Ferron Coal perfs fr/3,462' - 3,495' dwn 5-1/2 csg w/1,033 gals 15% HCL at 369 BPM & 4.8 psig. Caught press w/130 gals ppd. No significant form BD. Frac L/Ferron Coal perfs fr/3,462' - 3,495' w/37,986 gals frac G 20# slickwater, 89,419 gals 20# Delta 140 frac fld carrying 102,550 lbs 20/40 Brady sd, & 136,000 lbs 16/30 Brady sd. Frac Gradient .76. Flshd w/3,366 gals frac G 20# slickwater, 0.5 bbls short. Sd Conc 0.3 - 5.80 ppg. All sd coated w/sd wedge NT. ISIP 1,104 psig, 5" SIP 945 psig, 10" 877 psig, 15" 825 psig, ATP 1,730 psig. AIR 40.25 bpm. Max TP 2,025 psig. Max IR 42.43 bpm. Max sd conc 5.80 ppg. 3,058 BLWTR (L/Ferron). RD Halliburton. RU Bran-DEX WL. RIH & set 5-1/2" CBP @ 3,350'. POH w/ WL. Press tst CBP to 2,000 psig for 5". Tstd OK. RIH w/4" slick Csg Gun. Perf U/Ferron Coal w/3 JSPF 120 deg ph @ 3,311' - 3,313' & 3,317' - 3,320'. (15 holes, 22.7 gm, .41" dia, 120 deg ph). All dpts correlated w/Schlumberger RST/GR/CCL/CBL log Dated 10-23-06. POH. LD csg gun. RDMO Bran-Dex WLU. SICP 0 psig. Hole full. RU Halliburton frac crew. A U/Ferron Coal perfs fr/3,311' - 3,320' dwn 5-1/2" csg w/1,500 gals 15% HCL ac @ 5.0 BPM & 500 psig. Form BD @ 21.0 BPM & 1,600 psig. Frac U/Ferron Coal perfs fr/ 3,311' - 3,320' w/17,469 gals frac G 20# slickwater, 29,263 gals 20# Delta 140 frac fld carrying 33,050 lbs 20/40 Brady sd & 42,780 lbs 16/30 Brady sd. Frac Gradient 0.74. Flshd w/3,189 gals 20# Linear Gel, 3 bbls short. Sd Conc .30 - 5.5 ppg. All sd coated w/Sd Wedge NT. ISIP 1,009 psig, 5" SIP 899 psig, 10" SIP 821 psig, AIR 24.53 bpm, ATP 1,526 psig. Max TP 1,796 psig. Max IR 26.01 bpm, Max sd conc 5.5 ppg. 4,171 BLWTR (ttl). RDMO Halliburton. SWI. Susp rpts to further activity.

11/15/06 Cont rpt for AFE # 650457 to D & C Ferron Coal/sd. fr/ 11-2-06 to 11-15-06. SICP 0 psig. Blade road to get on loc. Inst rig anchors. MIRU BHWS rig# 1. ND frac vlv. NU BOP. PU & TIH w/4-3/4" blade bit, xo & 100 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Tgd fill @ 3,257'. U/Ferron Coal fr/3,311' - 3,320'. CBP @ 3,350'. RU swivel. TOH w/10 jts tbg. Backfill res pit. Build sep & mtr run pad. Set new CIP Inc 30" x 10', 500 psig WP, 2 ph, vert sep w/heated wtr bath (SN 4351), 250 MBTU burner & new Daniel 3" 150 C mtr run w/Daniel flgs (SN 0522011) fr/XTO stk. Dug trench fr/WH to sep & mtr run. Inst & conn welded 4" S40 FB pipe FL fr/WH tbg mnfd to sep inl. Inst & conn 6" welded S 40 FB pipe FL fr/WH csg mnfd to sep inl. Dug trench fr/sep to sales ln. Inst & conn welded 6" S40 FB pipe gas sales ln fr/mtr run to sales ln. Inst & conn 4" S 40 FB pipe fr/sep dmp to wtr ln. Backfill trench. Cln loc. SWI. SDFN. Susp rpts pending further activity. 4,171 BLWTR.

11/16/06 SICP 0 psig. TIH w/10 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Tgd fill @ 3,257'. U/Ferron Coal fr/3,311' - 3,320'. CBP @ 3,350'. RU pwr swivel. Estb circ. Hole full. CO fill & DO CBP fr/3,257' - 3,350' w/3 jts tbg. Circ cln. RD pwr swivel. TIH w/6 jts tbg. Tgd fill @ 3,525'. L/Ferron Coal/sd perfs @ 3,462' - 3,495'. PBTD @ 3,644'. RU pwr swivel. Estb circ. CO fill fr/3,525' - 3,644' (PBTD) w/4 jts tbg. Circ well cln. RD pwr swivel. TOH w/3 jts tbg. Bit @ 3,546'. RU swb tls. BFL @ surf. S. 0 BO, 228 BLW, 26 runs, 5 hrs, FFL @ 1,000' FS. Fld smpls on runs 1-7 showed dirty wtr w/lt sd, runs 8-23 showed cln wtr w/lt sd & coal, runs 24-26 showed cln wtr w/tr coal. RD swb tls. SICP 0 psig. TIH w/3 jts 2-7/8" tbg. Tgd 7' of fill @ 3,635'. TOH w/3 jts 2-7/8" tbg. Bit @ 3,546'. SWI. SDFN. Lost 325 BFW while circ for day. 4,268 BLWTR.

Swab	Zone:	Ferron			
	Event Desc:	Swab	Top Interval: 3,311		Bottom Interval: 3,495
		Swab	Beg	BBLS	
			FL	Rec	Comments
Time		Runs			
11:50:00 AM		1	0	10	BFL @ surface.

12:05:00 PM 24 100 211
 4:40:00 PM 1 1,000 8 FFL @ 1,000'.
Ttl Bbls: 228

11/17/06 SITP 0 psig, SICP 0 psig. TIH w/3 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Tgd no addl fill @ 3,637'. TOH w/3 jts tbg. Bit @ 3,546'. RU swb tls. BFL @ 1,000'. S. 0 BO, 229 BLW, 25 runs, 5 hrs, FFL @ 1,200' FS. Fld smpls on all runs showed cln wtr w/tr coal. RD swb tls. SICP 20 psig. TIH w/3 jts 2-7/8" tbg. Tgd no addl fill @ 3,637'. TOH w/108 jts tbg. LD BHA. TIH w/blr assy & 111 jts 2-7/8" tbg. CO fill fr/ 3,637 to PBTD @ 3,644'. TOH w/ 111 jts tbg. LD blr assy. TIH w/30' OPMA, 2705 Cavins Desander, 4' x 2-7/8" tbg sub, 2-7/8" SN & 108 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Ld tbg w/donut tbg hanger. SN @ 3,549.85'. EOT @ 3,604.05'. PBTD @ 3,644'. Ferron Coal perfs fr/3,311' - 3,495'. ND BOP. NU WH. SWI. SDFN. Rec 229 for day. 4,039 BLWTR.

Tubing **Location:** Lower
ZONE 1 Desc: Ferron Top Perf: 3,311 Btm Perf: 3,495 OH: No

Qty	Type	Description	Cond	Top Depth	Btm Depth	Length
108	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd Tubing	New	4	3,549	3,544.75'
1	Tubing	2-7/8" SN	New	3,549	3,550	1.10'
1	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd Tubing Sub	New	3,550	3,554	4.00'
1	Tubing	2-7/8" Cavins 2705 Desander	New	3,554	3,574	20.20'
1	Tubing	2-7/8" OPMA	New	3,574	3,604	30.00'
Total						3,600.05'
Landed @						3,600.05'

Swab **Zone:** Ferron
Event Desc: Swab Top Interval: 3,311 Bottom Interval: 3,495

Time	Swab Runs	Beg FL	BBLS Rec	Comments
7:30:00 AM	1	1,000	10	BFL @ 1,000'.
7:45:00 AM	23	1,000	209	
12:15:00 PM	1	1,200	10	FFL @ 1,200'.
		Ttl Bbls:	229	

11/18/06 SITP 0 psig, SICP 0 psig. Ppd 5 BFW & flshd tbg. PU & loaded 2-1/2" x 1-3/4" x 16' RHBC-DV pmp (XTO #117) w/1' X 1" stnr nip. TIH w/pmp, 1 - 7/8" stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 115 - 3/4" gr D skr d w/4 molded guides per rod, 19 - 7/8" gr D skr d w/3 molded guides pr rod, & 1-1/4" x 26' PR w/1-1/2" x 14' PR lnr. Seated pmp. PT tbg to 500 psig w/5 BFW for 10". Tstd ok. Rlsd press. LS pmp w/rig to 500 psig. Gd PA. HWO. RDMO BHWS rig #1. Surf equip not ready to start PU. 4,049 BLWTR.

11/27/06 Cont rpt for AFE # 651982 to D & C Ferron Coal well. Built WH mnfd. MIRU Nielsons Crane. Built gravel pad. Set used weatherford 8' x 24' x 16" cmt pad, used American 320-256-120" PU w/44" gearbox sheave (SN T25F1204ALST16), Marathon 50 hp elect motor (SN 09345170-4/24-5) w/8.5" motor sheave & 4 cp 210 belts fr/XTO stk. RDMO Nielsons Crane. Inst & conn new 3 hp Baldor elec motor (SN# F0602032541) fr/Industrial Electric on new Ebara 1" inl x 1" otl, 170 BWPD, centrifugal wtr trans pmp (SN# BG6210453) on sep wtr dump ln. Susp rpts pending further activity.

11/29/06 Cont rpt for AFE #651982 to D&C Ferron Coal well. SITP 0 psig, SICP 0 psig. Std PU @ 6:00 p.m., 11/28/06. Ppg @ 7 x 120" SPM. WO csg to build psig to first deliver gas sales.

11/30/06 Compl terminating ground sleeves. Cleaned up ROW. SDFN. Project complete.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-28-12X
2. NAME OF OPERATOR: XTO Energy Inc.		9. API NUMBER: 4301530699
3. ADDRESS OF OPERATOR: 2700 Farmington Ave K1 CITY Farmington STATE NM ZIP 87401		10. FIELD AND POOL, OR WILDCAT FERRON COAL
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1332' FNL & 582' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E
		12. COUNTY EMERY
		13. STATE UTAH

14. DATE SPURRED: 9/14/2006	15. DATE T.D. REACHED: 10/13/2006	16. DATE COMPLETED: 12/7/2006	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 6791 GL
18. TOTAL DEPTH: MD 3,820 TVD	19. PLUG BACK T.D.: MD 3,644 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) RST/GR/CBL/CCL			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
17 1/2	13 3/4 H40	48#		29		RM 70		0	0
12 1/4	8 5/8 J55	24#		315		V 240		0	0
7 7/8	5 1/2 J55	15.5#		3,692		CBM 214		0	0

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8	3,604							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) FERRON COAL	3,311	3,495			3,311 3,495	0.41	66	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
3311' - 3495'	A. w/2533 gals 15% HCl acid. Frac'd w/55,455 gals Frac G 20# slickwater, 118,682 gals 20# Delta 140 frac fld carrying 135,600# 20/40 Brady sd & 178,780# 16/30 Brady sd coated w/Sandwedge NT

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

RECEIVED

DEC 19 2006

DIV. OF OIL, GAS & MINING

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 12/7/2006		TEST DATE: 12/8/2006		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 24		WATER – BBL: 271		PROD. METHOD:							
CHOKE SIZE: N/A		TBG. PRESS. 40		CSG. PRESS. 100		API GRAVITY 1.31		BTU – GAS 1,748		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 24		WATER – BBL: 271		INTERVAL STATUS:	

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

TO BE SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				MANCOS MARKER UPPER FERRON SS LWR FERRON SS	3.182 3.310 3.505

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.


NAME (PLEASE PRINT)

HOLLY C. PERKINS

TITLE

REGULATORY COMPLIANCE TECH

SIGNATURE



DATE

12/14/2006

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

4301530699

FORM 9

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER. UTU-73965
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR: 2700 Farmington, Bldg K-1 Farmington CITY STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME
4. LOCATION OF WELL FOOTAGES AT SURFACE: 660' FSK & 792' FEL		8. WELL NAME and NUMBER LM LEMMON #10-01
5. PHONE NUMBER: (505) 324-1090		9. API NUMBER: Various (See attached)
6. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SESE 10 17S 08E		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE

COUNTY: EMERY

STATE: UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start 1/1/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion	<input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired wells from Chevron/Texaco on August 1, 2004. Chevron/Texaco failed to file a Notice of Intent to surface commingle these wells and XTO Energy Inc. was unaware until recently that nothing had been filed. We are including with this application for surface commingle a list of the wells in Emery County and a spreadsheet showing production figures for these wells. Each well has its own meter then runs through a central delivery point where allocations are made.

XTO Energy Inc. is requesting approval for the commingle of these wells as well as off-lease measurement. As wells are drilled, additional sundries will be submitted to add to our surface commingle.

COPY SENT TO OPERATOR
Date: 6-12-07
Initials: RM

NAME (PLEASE PRINT) HOLLY C. PERKINS	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE <i>Holly C. Perkins</i>	DATE 5/15/2007

This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 6/11/07
BY: *[Signature]*

Federal Approval Of This
Action Is Necessary

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Utah Wells Surface Commingled at Huntington CDP

Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

Utah Wells Surface Commingled at Huntington CDP

State of Utah FO 02-186	43-015-30533	Producing	State
State of Utah FO 02-188	43-015-30553	Producing	State
State of Utah GG 03-122	43-015-30499	Producing	State
State of Utah GG 04-115	43-015-30504	Producing	State
State of Utah HH 03-133	43-015-30500	Producing	State
State of Utah II 36-95	43-015-30509	Producing	State
State of Utah II 36-96	43-01530508	Shut In	State
State of Utah KK 32-144	43-015-30567	Producing	State
State of Utah QQ 31-201	43-015-30592	Producing	State
State of Utah SS 22-165	43-015-30520	Producing	State
State of Utah T 36-10	43-015-30268	Producing	State
State of Utah T 36-100	43-015-30506	Producing	State
UP&L 06-102	43-015-30441	Producing	State
UP&L 06-103	43-015-30483	Producing	State
UP&L 06-104	43-015-30442	Producing	State
UP&L Federal 01-101	43-015-30511	Producing	Federal
Utah Federal 01-205D	43-015-30589	Producing	Federal
* Utah Federal 16-7-35-21	43-015-30602	Producing	Federal
* Utah Federal 16-7-35-32	43-015-30603	Producing	Federal
X Utah Federal 17-7-12-22D	43-015-30605	Producing	Federal
Utah Federal 17-7-12-24D	43-015-30604	Producing	Federal
+ Utah Federal 17-7-12-42	43-015-30591	Producing	Federal
Utah Federal 17-7-12-43	43-015-30601	Producing	Federal
Utah Federal 17-7-3-41D	43-015-30697	Producing	Federal
Utah Federal KK 01-140	43-015-30507	Producing	Federal
Utah Federal KK 01-141	43-015-30559	Producing	Federal
Utah Federal M 06-25	43-015-30292	Producing	Federal
WH Leonard 15-127	43-015-30485	Producing	State
Wm S Ivie 09-118	43-015-30443	Producing	State
Zion's Federal 35-135R	43-015-30521	Producing	Federal
+ Zion's Federal 17-7-2-11	43-015-30590	Producing	Federal
Zion's Federal 35-137	43-015-30587	Producing	Federal

Utah Wells Surface Commingled at Orangeville CDP

Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-95	43-015-30509	Producing	State	
State of Utah II 36-96	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal	
USA 11-72	43-015-30387	Producing	Federal	
USA 18-7-11-23	43-015-30640	Producing	State	
USA 34-80	43-015-30389	Shut In	Federal	
USA 34-82	43-015-30390	Producing	Federal	
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal	
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal	
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal	
Utah Federal D 34-12	43-015-30282	Producing	Federal	
Utah Federal D 35-13	43-015-30285	Producing	Federal	
Utah Federal D 35-14	43-015-30286	Producing	Federal	
Utah Federal D 35-15	43-015-30287	Producing	Federal	
Utah Federal H 06-21	43-015-30294	TA	Federal	
Utah Federal P 10-42	43-015-30276	Producing	Federal	
Utah Federal P 10-43	43-015-30277	Producing	Federal	
Utah Federal P 10-47	43-015-30258	Producing	Federal	
Utah Federal Q 04-44	43-015-30280	Producing	Federal	
Utah Federal R 09-45	43-015-30275	Producing	Federal	
Utah Federal S 08-46	43-015-30274	Producing	Federal	
Utah State 01-76	43-015-30381	Producing	State	
Utah State 36-78	43-015-30382	Producing	State	

Apr-05

ington Wells

				FIELD ESTIMATED PRODUCTION										ACTUAL ALLOCATED SALES									
WELL No.	Days On	MONTHLY WATER PRODUCTION	Coastal Statement	PROD %	FIELD EST PROD	In Gas	Lse Use Gas	Vented CO2	Vented Gas	VENIED GAS	ADJ	FIELD ESTIMATED SALES	ALLOCATED SALES	Lsa Use Gas (n) 216	Vented CO2	Vented Gas	VENTED GAS	ADJ	FIELD PRODUCTION				
	10-01	30	435	1478	0.00488716	1479	45	36	98	1708	98	179	1299	1246	91	98	1708	179	1425				
	T33-10	30	2687	18292	0.06048442	18298	45	447	1708	2280	1708	2200	16099	15424	492	1708	2280	2200	17624				
	M08-25	30	723	16969	0.05610978	16975	45	414	2280	2280	2739	14236	14308	459	2280	2280	2739	17047	0				
	H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
	07-108	30	679	5052	0.01673803	5064	45	124	789	789	658	4106	4268	169	789	789	658	5226					
	09-119	30	185	725	0.0024006	725	45	18	108	108	171	655	612	53	108	108	38	783					
	10-124	30	129	951	0.00314458	951	45	23	38	38	106	845	802	68	38	38	38	909					
	08-102	30	823	20112	0.06650244	20119	45	319	2219	2219	2755	17354	16959	536	2219	2219	2755	19714					
	06-104	30	803	12922	0.04272795	12925	45	319	2156	2156	2516	10410	10895	350	2156	2156	2516	835					
	06-104	30	803	12922	0.04272795	12925	45	319	2156	2156	2516	10410	10895	350	2156	2156	2516	835					
	06-118	30	163	757	0.00263536	797	45	22	80	80	47	752	758	67	80	80	100	164					
	09-120	30	214	899	0.00297264	899	45	22	80	80	47	752	758	67	80	80	100	164					
	18-7-23-23	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0					
	17-8-15-33	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0					
	10-123	30	261	1348	0.0044573	1348	45	33	89	89	167	1182	1137	78	89	89	89	167					
	10-125	30	266	536	0.00177234	536	45	13	32	32	90	446	452	58	32	32	32	90					
	11-129	29	0	396	0.00130942	396	44	10	16	16	59	327	334	53	16	16	16	59					
	11-130	30	1847	162	0.000503567	162	45	4	7	7	56	109	137	49	7	7	7	56					
	16-121	30	275	757	0.0026031	757	45	18	42	42	105	652	638	93	42	42	42	105					
	05-107	29	242	8230	0.02721336	8233	44	201	1397	1397	1641	6591	6940	244	1397	1397	1397	1641					
	05-108	30	611	4934	0.01631479	4936	45	120	830	830	955	3940	4160	165	830	830	830	955					
	05-109	30	113	1252	0.00413987	1252	45	31	133	133	209	1044	1056	76	133	133	133	209					
	05-110	30	3	1462	0.00483426	1463	45	36	194	194	275	1188	1233	81	194	194	194	275					
	05-103	30	946	9133	0.03019922	9136	45	223	1241	1241	1509	7627	7701	268	1241	1241	1241	1509					
	15-126	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0					
	15-127	30	1452	3530	0.01167232	3531	45	56	226	226	357	3174	2977	131	226	226	226	357					
	08-111	29	143	1513	0.00500289	1514	44	37	203	203	283	1230	1275	80	203	203	203	283					
	08-112	30	118	1326	0.00438456	1326	45	32	143	143	220	1106	1118	77	143	143	143	220					
	08-113	30	0	756	0.00249979	756	45	18	108	108	271	585	637	63	108	108	108	271					
	07-105	30	909	5760	0.02235265	5762	45	165	1197	1197	1407	5355	5700	210	1197	1197	1197	1407					
	03-122	30	0	456	0.00150781	456	45	11	30	30	85	370	385	58	30	30	30	85					
	03-133	30	102	331	0.00109449	331	45	8	18	18	71	260	279	53	18	18	18	71					
	09-117	30	37	945	0.00312805	946	45	23	63	63	123	480	508	60	63	63	63	123					
	04-116	30	114	603	0.00199388	603	45	15	130	130	204	982	1000	74	130	130	130	204					
	04-115	30	258	1185	0.00392163	1185	45	29	5000	5000	5896	28955	29376	896	5000	5000	5000	5896					
	T36-100	30	3714	34839	0.11519881	34851	45	851	462	462	606	3460	3428	144	462	462	462	606					
	01-140	30	1506	4065	0.01344135	4068	45	99	2937	2937	3580	20907	20640	643	2937	2937	2937	3580					
	01-101	30	1199	24478	0.08093908	24486	45	586	162	162	320	4312	3904	158	162	162	162	320					
	22-165	30	1690	4630	0.01530958	4632	45	113	142	142	179	1323	1266	37	142	142	142	179					
	35-135R	30	4133	1501	0.00496321	1502	0	37	142	142	179	4325	3917	158	142	142	142	179					
	14-171	30	3033	4645	0.01535918	4647	45	113	1062	1062	1327	7689	7600	265	1062	1062	1062	1327					
	35-139	30	734	9013	0.02980243	9016	45	220	42	42	101	474	485	59	42	42	42	101					
	02-186	30	193	575	0.0019013	575	45	14	396	396	570	4730	4468	174	396	396	396	570					
	35-138	30	555	5299	0.0175217	5301	45	129	48	48	107	452	471	59	48	48	48	107					
	03-161	30	61	558	0.00184509	558	45	14	48	48	113	811	778	68	48	48	48	113					
	02-188	30	176	923	0.003052	923	45	23	283	283	382	1804	1659	93	283	283	283	382					
	14-131	30	793	1967	0.00650409	1968	45	48	5540	5540	6351	1827	1862	99	5540	5540	5540	6351					
	01-141	30	59	2208	0.00730098	2209	45	54	283	283	382	25047	25466	811	5540	5540	5540	6351					
	32-144	30	3738	31387	0.10378441	31398	45	766	538	538	605	2155	2327	57	538	538	538	605					
	07-145	30	672	2760	0.00912623	2761	0	67	1276	1276	1560	10057	9792	284	1276	1276	1276	1560					
	35-137	30	1356	11613	0.0383595	11617	0	284	257	257	322	2338	2242	65	257	257	257	322					
	01-205D	30	4123	2659	0.00879225	2660	0	55	4755	4755	5621	29871	29917	866	4755	4755	4755	5621					
	31-201	30	1581	35480	0.11731834	35492	0	866	4755	4755	5621	29871	29917	866	4755	4755	4755	5621					
			43726	302425	1	302529	1930	5	7383	38990	38990	48303	5	254225	5	255009	9312	38990	48302	303311			
												ETU		104 SALES MTR	255006								

IPELINE

LE WELLS FROM CLASIA STATEMENT

	20777				SALES DIFFERENCE	85.6	JC137.4
	0						
	7604				7604	0	
	2448		2448				
	0		0				
	974						
Id statement + memon	31803		295682	2448	7604	0	

385211	597033		597137	4379	14975	59724	59724	79077	516060	514853	19355	59724	59724	59724	79079	593932
--------	--------	--	--------	------	-------	-------	-------	-------	--------	--------	-------	-------	-------	-------	-------	--------

OCT 12 2004

FORM 9

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Various Leases
2. NAME OF OPERATOR: XTO ENERGY INC. <i>N2615</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Bldg K, Sui. Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: See attached list
5. LOCATION OF WELL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER: Multiple
		10. FIELD AND POOL, OR WILDCAT: Buzzard Bench
		COUNTY: Emery
		STATE: UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC.
for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

RECEIVED
MAY 18 2007
DIV. OF OIL, GAS & MINING

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. *N0210*

NAME (PLEASE PRINT)

James L. Death

TITLE

Vice President-Land

SIGNATURE

James L. Death

DATE

8/16/04

(This space for State use only)

APPROVED

9/30/2004

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

(5/2000)

RECEIVED

SEP 28 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-67532
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1815' FNL & 897' FWL		8. WELL NAME and NUMBER: FEDERAL A 18-7-26 #12
QTR/CTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 26 18S 07E		9. API NUMBER: 4301530445
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: BUZZARD BENCH ABO
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to surface commingle the following two wells into our Orangeville CDP:

Federal A 18-7-26 #12; Sec 26-T18S-R07E; 1815' FNL & 897' FWL; 43-015-30445; UTU-67532; Buzzard Bench
Federal T 18-7-22 #34; Sec 22-T18S-R07E; 539' FSL & 1831' FEL; 43-015-30452; UTU-68535; Buzzard Bench

Both of these wells have their own wellhead allocation meter. Both wells will have the sales point or custody transfer at the Orangeville System.

COPY SENT TO OPERATOR
Date: 7-11-05
Initials: CHO

NAME (PLEASE PRINT) MOLLY C. PERKINS TITLE REGULATORY COMPLIANCE TECH
SIGNATURE Molly C. Perkins DATE 6/23/2005

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED

JUN 29 2005

DIV. OF OIL, GAS & MINING

(5/2000)

Date: 7/8/05 (See Instructions on Reverse Side)

By: Dustin Ducret

Dustin Ducret??

IN WELLS FROM COASTAL STATEMENT

	0	302425			
	38990				
	104	104			
	256029				
s Check #	0				
s Check #2	0			0	
	7383			7383	0
	1931		1930 5		
	0				
	304437	302529	1930 5	7383	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (505) 333-3100		8. WELL NAME and NUMBER: MULT St of Ut 17-8-28-12X
4. LOCATION OF WELL FOOTAGES AT SURFACE: MULTIPLE		9. API NUMBER: MULTIPLE 43 015 30699
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: 17S 8E 28		10. FIELD AND POOL, OR WILDCAT:

COUNTY: EMERY


STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SURFACE
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	COMMINGLE

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. applied for surface commingle on the attached list of wells on 7/5/07 and State of UT DOGM approval was received on 7/13/07. Due to the rejection of the Federal application, XTO would like to withdraw the commingling application and subsequent work will not be done.

NAME (PLEASE PRINT) LORRI D. BINGHAM TITLE REGULATORY COMPLIANCE TECH
SIGNATURE  DATE 9/23/2008

(This space for State use only)

RECEIVED
SEP 29 2008

Utah Wells Surface Commingled at Huntington CDP			
Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-115	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

should be
on Orangeville
CDP

RECEIVED

SEP 29 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48218
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1332' FNL & 582' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-28-12X
		9. API NUMBER: 4301530699
		10. FIELD AND POOL, OR WILDCAT: BUZZ BENCH/FERRON SS
		COUNTY: EMERY
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 6/1/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. plans to plug and abandon this well per the attached procedure. Please see also, the attached current and proposed wellbore diagrams.

COPY SENT TO OPERATOR

Date: 2-24-2009

Initials: KS

NAME (PLEASE PRINT) LORRI D. BINGHAM	TITLE SR. REGULATORY COMPLIANCE TECH
SIGNATURE 	DATE 1/15/2009

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 2/11/09

BY: 

(See Instructions on Reverse Side)

* See conditions of Approval (Attached)

RECEIVED
JAN 21 2009

DIV. OF OIL, GAS & MINING

JDB _____

TWD _____

APPROVED _____

State of Utah 17-08-28-12X
1,332' FNL & 582' FWL, Sec 28, T17S, R8E
Emery County, UT

Plug & Abandon Procedure

Formation: Ferron Coal/Sand.

Surf Csg: 8-5/8" csg @ 315'. Csg cmt'd w/ 240 sks Type V Cmt. Circ cmt to surf.

Prod Csg: 5-1/2", 15.5#, J-55 csg @ 3,692'. Csg cmt'd w/ 68 sks CBM Lite and 165 sks Type III Lite. Did not cmt to surf.

Tbg: 2-7/8", 6.5#, J-55, EUE, 8 rd. EOT @ 3,604'. SN @ 3,550'.

Rods: 19 - 7/8" Grade 'D' Rods, 115 - 3/4" Grade 'D' Rods, & 6 - 1-1/2" SBS.

Pump: 2-1/2" x 1-3/4" x 16' RHBC Insert

Current Status: Producing via PU.
10 mcfpd & 0 bwpd

1. Notify Dustin Doucet, Utah Division of Oil, Gas & Mining at 801-538-5281, 48 hrs in advance of pending operations.
2. Set 1 flowback tnk. MIRU PU w/ pmp & pit.
3. TOH & LD rod string & insert pmp.
4. Drop 2-7/8" SV. PT tbg to 1,000 psi for 10". Retr SV.
5. ND WH. NU BOP.
6. TOH w/ 2-7/8" tbg. LD the BHA consisting of a Cavins Desander & OPMA.
7. PU & TIH w/ 4-3/4" bit, 5-1/2" csg scr, SN, & 2-7/8" tbg to 3,250'.
8. TOH w/ 2-7/8" tbg & LD bit & csg scr.
9. MIRU WL. RIH w/ 5-1/2" CIBP. Set CIBP @ 3,305'. (Correlate depth w/ RST log & GR/CCL/CBL log ran on October 23, 2006.) POOH & RD WL.
10. MIRU cmt pmp trk.
11. TIH w/ 2-7/8" tbg to 3,305'. Load hole & circ cln w/ gelled wtr. PT csg to 500 psi for 10". Rls press.

12. **PLUG #1:** Mix 20 sks Type V cmt (15.6 ppg, 1.18 cuft/sk) & spot a 180' balanced plug inside the 5-1/2" csg fr/ 3,305' – 3,125'.
13. TOH & LD 2-7/8" tbg.
14. RU WL. RIH & perforate 3 holes in the 5-1/2" csg @ 370' w/ HSC gun. POOH & RDMO WL. ND BOP.
15. RU cmt pmp trk. Open the 5-1/2" x 8-5/8" bradenhead vlv. Tie pmp trk onto 5-1/2" csg. Load hole & establish circ w/ wtr.
16. **PLUG #2:** Mix 125 sks Type V cmt (15.6 ppg , 1.18 cuft/sk) & pmp it dwn the 5-1/2" csg & circ cmt up the 5-1/2" x 8-5/8" annulus. (The entire 5-1/2" csg & 5-1/2" x 8-5/8" annulus will be filled w/ cmt fr/ 370' back to surf. Cmt vol includes 20% excess.)
17. Monitor well for cmt fall back & top off if necessary. RDMO cmt pmp trk.
18. Cut off WH below surf csg. Install P&A marker. RDMO PU.
19. Haul all equip to XTO yard.
20. The location will have to be reclaimed since no further activity is planned on this well pad.

REGULATORY REQUIREMENTS:

- Utah Division of Oil, Gas & Mining approval.
- LOI to interest owners


WELL SERVICES:

- Pulling Unit
- Wireline Services
- Cementing Services
- Dirt Work & Reseeding Services

MATERIALS:

- NA

KB: 6,795'
GL: 6,791'
CORR: 4.0'



STATE OF UTAH 17-08-28-12X WELLBORE DIAGRAM

DATA

LOCATION: 1,332' FNL & 582' FWL, SEC 28, T-17-S, R-8-E
COUNTY/STATE: EMERY COUNTY, UT
FIELD: FERRON, BUZZARD BENCH
FORMATION: FERRON COAL
FEDERAL LEASE: API #: 43-015-30699 XTO ACCTG #: 114202
SPUD DATE: 09/14/06 **COMPL DATE:** 11/01/06
IP: 271 bwpd & 24 mcfpd
PRODUCTION METHOD: PU
TBG: 2-7/8", 6.5#, J-55, EUE, 8RD TBG. EOT @ 3,604'. SN @ 3,550'.
PERFS: 3,311' - 3,313', 3,317' - 3,320', 3,462' - 3,465', & 3,481' - 3,495',

HISTORY:

09/14/06: MIRU STEWART BROS DRLG. SPURRED 17" HOLE & DRLD 17" HOLE TO 29'. SET 13-3/8" COND CSG @ 29' KB.
09/15/06: SPURRED 12-1/4" HOLE.
09/17/06: DRLD 12-1/4" HOLE TO 323' KB. SET 8-5/8", 24#, J-55, ST&C SURF CSG @ 315' KB & CMT W/ 240 SKS TYPE V W/ ADDITIVES. CIRC 20 BBLS CMT TO SURF.
09/18/06: SPURRED 7-7/8" HOLE.
09/24/06: TWISTED OFF DRL STRG @ 1,695'. LEFT 6 COLLARS, MUD MOTOR, & BIT IN HOLE. TRIED TO SPEAR & RECOVERED ONLY 2 DC.
09/26/06: TRIED TO FISH W/ OVERSHOT & JARS. COULD NOT FISH. RLS AIR PACKAGE & MI STEEL MUD PITS.
09/27/06: MIX MUD. MIRU HALLIBURTON. SPOT CMT PLUG. POOH. WOC.
09/28/06: DRESS CMT PLUG TO 1,365'.
09/29/06: START SLIDE DRLG W/ MUD.
10/06/06: LOSS CIRC @ 1,962'. RAN OUT OF WTR & MUD. PULL UP INTO SURF CSG. WAIT ON AIR PACKAGE.
10/07/06: TIH. UNLOAD HOLE & CLN OUT 70' FILL ON BOT. DRL W/ AIR-MIST TO 2,075'.
10/13/06: REACHED DRILLER'S TD OF 3,820'. CIRC F/ LOGS.
10/15/06: MIRU SCHLUMBERGER. LOGS STOPPED @ 3,278'. RDMO SCHLUMBERGER.
10/16/06: PU & TIH W/ 82 JTS 5-1/2", 15.5#, J-55, LT&C CSG TO 3,692' KB. FC @ 3,644' KB. MARKER JT @ 2,303' KB. MIRU HALLIBURTON. CMT'D 5-1/2" CSG W/ 68 SK CBM LITE CMT + ADDITIVES FOLLOWED BY 165 SK TYPE III LITE CMT + ADDITIVES. DID NOT CIRC CMT TO SURF. RDMO HALLIBURTON. RLSD DRLG RIG (10/16/06).
10/23/06: RAN CASED HOLE RST-SIGMA & RST-IC LOGS FR/ 3,623' - 3,023'. RAN GR/CCL/CBL LOG FR/ 3,641' - 200'. TOC @ 2,300'.
11/01/06: PERF LOWER FERRON COAL FR/ 3,462' - 3,465' & 3,481' - 3,495' W/ 3 SPF. FRAC LOWER FERRON COAL PERFS FR/ 3,462' - 3,495' DWN 5-1/2" CSG W/ 1,030 GALS 15% HCL, 37,980 GALS 20# LINEAR GEL, 89,400 GALS 20# XL GEL, 102,550# 20/40 SD, & 136,000# 16/30 SD. FLSHD W/ 3,365 GALS. MAX SD = 5.8 PPG. ATP=1,730 PSI. MAX TP=2,025 PSI. AIR=40.2 BPM. ISIP=1,105 PSI. SET CBP @ 3,350'. TSTD CBP TO 2,000 PSI. TSTD OK. PERF UPPER FERRON COAL FR/ 3,311' - 3,320' W/ 3 SPF. FRAC UPPER FERRON COAL PERFS FR/ 3,311' - 3,320' DWN 5-1/2" CSG W/ 1,500 GALS 15% HCL, 17,470 GALS 20# LINEAR GEL, 29,265 GALS 20# XL GEL, 33,050# 20/40 SD, & 42,800# 16/30 SD. FLSHD W/ 3,190 GALS. MAX SD = 5.5 PPG. ATP=1,525 PSI. MAX TP=1,795 PSI. AIR=24.5 BPM. ISIP=1,010 PSI.
11/15/06: MIRU WORKOVER UNIT. CLN OUT SD, DO CBP, & CLN OUT SD TO PBD @ 3,644'.

11/16/06: MADE 25 SWAB RUNS. FLD SAMPLES ON ALL RUNS SHOWED CLN WTR W/ TR COAL. CLN OUT TO PBTD @ 3,644'. LANDED 2-7/8" TBG W/ SN @ 3,550' & EOT @ 3,604'.


11/17/06: TIH W/ 2-1/2"x1-3/4"x16' RHBC PMP, 6 – 1-1/2" SBS W/ 4 STABILIZER RODS SPACED BTW, 115 – 3/4" GRADE D GUIDED RODS, 19 – 7/8" GRADE D GUIDED RODS, & A 1-1/4"x26' PR. HWO. RDMO WORKOVER UNIT.

11/26/06: SET AMERICAN 320-256-120 PU.

11/28/06: STD PU. PPG @ 7x120" SPM.

12/07/06: FIRST DELIVERED TO SALES @ 271 BWPD & 24 MCFPD.

KB: 6,795'
GL: 6,791'
CORR: 4.0'



STATE OF UTAH 17-08-28-12X P&A WELLBORE DIAGRAM

DATA

LOCATION: 1,332' FNL & 582' FWL, SEC 28, T-17-S, R-8-E
COUNTY/STATE: EMERY COUNTY, UT
FIELD: FERRON, BUZZARD BENCH
FORMATION: FERRON COAL **TOP OF FERRON:** 3,310'
FEDERAL LEASE: **API #:** 43-015-30699 **XTO ACCTG #:** 114202
SPUD DATE: 09/14/06 **COMPL DATE:** 11/01/06
IP: 271 bwpd & 24 mcfpd
PRODUCTION METHOD: PU
TBG: 2-7/8", 6.5#, J-55, EUE, 8RD TBG. EOT @ 3,604'. SN @ 3,550'.
PERFS: 3,311' - 3,313', 3,317' - 3,320', 3,462' - 3,465', & 3,481' - 3,495',

HISTORY:

xx/xx/xx: WELL DIAGRAM OF FINAL ABANDONMENT IS SHOWN ON LEFT..



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

CONDITIONS OF APPROVAL TO PLUG AND ABANDON WELL

Well Name and Number: ST of UT 17-8-28-12X (Rigskid)
API Number: 43-015-30699
Operator: XTO Energy Inc.
Reference Document: Original Sundry Notice dated January 15, 2009,
received by DOGM on January 21, 2009.

Approval Conditions:

1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.
2. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration.
3. All annuli shall be cemented from a minimum depth of 100' to the surface.
4. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.
5. If there are any changes to the procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 (ofc) or 801-733-0983 (home) prior to continuing with the procedure.
6. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.

Dustin K. Doucet
Petroleum Engineer

February 11, 2009

Date



API Well No: 43-015-30699-00-00

Permit No:

Well Name/No: ST OF UT 17-8-28-12X(RIGSKID)

Company Name: XTO ENERGY INC

Location: Sec: 28 T: 17S R: 8E Spot: SWNW

Coordinates: X: 496889 Y: 4351907

Field Name: BUZZARD BENCH

County Name: EMERY

String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)	Capacity (f/cf)
HOL1	29	17.5			
COND	29	13.375	48	29	
HOL2	315	12.25			
SURF	315	8.625	24	315	
HOL3	3692	7.875			
PROD	3692	5.5	15.5	3692	7.483
T1	3604	2.875			

$$8\frac{5}{8}'' \times 5\frac{1}{2}'' \rightarrow 5.192$$

$$7\frac{7}{8}'' \times 5\frac{1}{2}'' (158) \rightarrow 3.5419$$

Cement from 29 ft.

Conductor: 13.375 in. @ 29 ft.

Hole: 17.5 in. @ 29 ft.

Cement from 315 ft. to surface

Surface: 8.625 in. @ 315 ft.

Hole: 12.25 in. @ 315 ft.

Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
COND	29		UK	70
PROD	3692	2300	UK	214
SURF	315	0	UK	240

outside
Below shoe

$$55' / (1.18) (3.5419) = 135x$$

Above shoe

$$315' / (1.18) (5.192) = 525x$$

Inside

$$370' / (1.18) (7.483) = 425x$$

$$\text{Total} = 1075x$$

$$\text{Prod} = 125x \quad \checkmark \quad \text{o.k.}$$

Perforation Information

Top (ft sub)	Bottom (ft sub)	Shts/Ft	No Shts	Dt Squeeze
3311	3495			

Formation Information

Formation	Depth
BLUGT	0
FRSD	3310

Cement from 3692 ft. to 2300 ft.

Tubing: 2.875 in. @ 3604 ft.

Production: 5.5 in. @ 3692 ft.

Hole: 7.875 in. @ 3692 ft.

Hole: Unknown

TD: 3820 TVD: 3620 PBD: 3644

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48218
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1332' FNL & 582' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 28 17S 8E		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-28-12X
PHONE NUMBER: (505) 333-3100		9. API NUMBER: 4301530699
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: BUZZ BENCH/FERRON SS
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 6/24/2009	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. plugged & abandoned this well per the attached Morning Report.

NAME (PLEASE PRINT) BARBARA A. NICOL

TITLE REGULATORY CLERK

SIGNATURE

Barbara A. Nicol

DATE

6/29/2009

(This space for State use only)

RECEIVED
JUL 01 2009
DIV. OF OIL, GAS & MINING

EXECUTIVE SUMMARY REPORT

6/23/2009 - 6/29/2009
Report run on 6/29/2009 at 10:52 AM

State of Utah 17-08-28-12X

Section 28-17S-08E, Emery, Utah, Buzzard Bench

Objective: P&A Well

Date First Report: 6/17/2009

Method of Production: Plugged

6/23/2009 SICP 0 psig. Cmt @ top of 5 -1/2", unable to see cmt in 8 -5/8" ann. NU & ppd 70 BFW to fill 8 - 5/8" x 5-1/2" ann. TIH w/120' of 3/4" pvc pipe, ppd a 32 sxs, 15.6 ppg, type 2 cmt plg fr/120' to surf. Cmt fell back. Ppd a second 32 sxs type 2 cmt plg fr/37' - surface. Installed P & A marker & RDMO. Fin rpt for P & A ops.

6/24/2009 ===== State of Utah 17-08-28-12X =====
We have P&A the State of Utah 17-08-28-12X @ 8:00 a.m., Wednesday, 6/24/09 for economics. Well site is now P&A. Location still needs to be reclaimed.